



ASSET MANAGEMENT PLAN

Berrigan Shire Council

Transport Asset Management Plan 2020

| Document Control | | Asset Management Plan | | | |
|------------------|------------|-----------------------|--------|----------|----------|
| Document ID : | | | | | |
| Rev No | Date | Revision Details | Author | Reviewer | Approver |
| V1 | 20.01.2021 | | ESM | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

The entity can choose either template to write/update their plan regardless of their level of asset management maturity and in some cases may even choose to use only the Executive Summary.

The illustrated content is suggested only and users should feel free to omit content as preferred (e.g. where info is not currently available).

This Asset Management Plan may be used as a supporting document to inform an overarching Strategic Asset Management Plan.

Contents

| | | |
|------------|--|-----------|
| 1.0 | EXECUTIVE SUMMARY | 5 |
| 1.1 | The Purpose of the Plan | 5 |
| 1.2 | Asset Description | 5 |
| 1.3 | Levels of Service | 6 |
| 1.4 | Future Demand | 6 |
| 1.5 | Lifecycle Management Plan | 6 |
| 1.6 | Financial Summary | 6 |
| 1.7 | Asset Management Practices | 8 |
| 1.8 | Monitoring and Improvement Program | 8 |
| 2.0 | Introduction | 9 |
| 2.1 | Background | 9 |
| 2.2 | Goals and Objectives of Asset Ownership | 12 |
| 2.3 | Community Consultation | 14 |
| 3.0 | LEVELS OF SERVICE | 15 |
| 3.1 | Customer Research and Expectations | 15 |
| 3.2 | Strategic and Corporate Goals | 16 |
| 3.3 | Legislative Requirements | 17 |
| 3.4 | Customer Values | 18 |
| 3.5 | Customer Levels of Service | 18 |
| 3.6 | Technical Levels of Service | 20 |
| 4.0 | FUTURE DEMAND | 29 |
| 4.1 | Demand Drivers | 29 |
| 4.2 | Demand Forecasts | 29 |
| 4.3 | Demand Impact and Demand Management Plan | 29 |
| 4.4 | Asset Programs to meet Demand | 29 |
| 4.5 | Climate Change and Adaption | 30 |
| 5.0 | LIFECYCLE MANAGEMENT PLAN | 31 |
| 5.1 | Background Data | 31 |
| 5.2 | Operations and Maintenance Plan | 34 |
| 5.3 | Renewal Plan | 35 |
| 5.4 | Summary of future renewal costs | 38 |
| 5.5 | Acquisition Plan | 39 |
| 5.6 | Disposal Plan | 41 |

| | | |
|-------------|---|-----------|
| 6.0 | RISK MANAGEMENT PLANNING | 42 |
| 6.1 | Critical Assets..... | 42 |
| 6.2 | Risk Assessment..... | 42 |
| 6.3 | Infrastructure Resilience Approach | 47 |
| 6.4 | Service and Risk Trade-Offs | 48 |
| 7.0 | FINANCIAL SUMMARY | 49 |
| 7.1 | Financial Statements and Projections..... | 49 |
| 7.2 | Funding Strategy..... | 50 |
| 7.3 | Valuation Forecasts | 50 |
| 7.4 | Key Assumptions Made in Financial Forecasts | 51 |
| 7.5 | Forecast Reliability and Confidence..... | 51 |
| 8.0 | PLAN IMPROVEMENT AND MONITORING | 53 |
| 8.1 | Status of Asset Management Practices | 53 |
| 8.2 | Improvement Plan | 53 |
| 8.3 | Monitoring and Review Procedures | 54 |
| 8.4 | Performance Measures | 54 |
| 9.0 | REFERENCES | 55 |
| 10.0 | APPENDICES | 56 |
| Appendix A | Acquisition Forecast..... | 56 |
| Appendix B | Operation Forecast | 59 |
| Appendix C | Maintenance Forecast | 60 |
| Appendix D | Renewal Forecast Summary | 61 |
| Appendix E | Disposal Summary..... | 91 |
| Appendix F | Budget Summary by Lifecycle Activity | 92 |

1.0 EXECUTIVE SUMMARY

1.1 The Purpose of the Plan

Asset management planning is a comprehensive process ensuring delivery of services from infrastructure is financially sustainable.

This Asset Management Plan (AM Plan) details information about infrastructure assets with actions required to provide an agreed level of service in the most cost-effective manner while outlining associated risks. The plan defines the services to be provided, how the services are provided and what funds are required to provide over the 20 year planning period. The Asset Management Plan will link to a Long-Term Financial Plan which typically considers a 10 year planning period.

This plan covers the infrastructure assets that provide transport facilities including roads, bridges, carparks, kerb and gutter and footpaths.

1.2 Asset Description

The Transport assets network comprises:

| Asset category | Dimension (km) | Replacement Value (\$000) |
|------------------------------|----------------|---------------------------|
| Arterial Road | 9.924 | \$4,340.10 |
| Asphalt Footpath | 7.680 | \$358.98 |
| Asphalted Concrete Footpath | 1.502 | \$599.56 |
| Barrier Kerb and Gutter | 62.36 | \$6,610.12 |
| Brick Kerb and Gutter | 0.196 | \$20.77 |
| Carpark | 0.340 | \$272.65 |
| Collector Gravel Road | 17.533 | \$1,235.06 |
| Collector Sealed Road | 158.905 | \$27,936.90 |
| Concrete Footpath | 24.094 | \$ 3,021.88 |
| Firetrail | 37.915 | \$2,036.76 |
| Gravel Footpath | 2.983 | \$53.72 |
| Kerb Only | 5.539 | \$587.18 |
| Mountable Kerb and Gutter | 58.211 | \$6,170.38 |
| Pattern Concrete Footpath | 1.503 | \$514.24 |
| Paving Footpath | 0.160 | \$66.65 |
| Property Access Rural | 377.465 | \$16,346.04 |
| Property Access Urban | 24.587 | \$1,083.92 |
| Quarry Dust Footpath | 13.037 | \$274.86 |
| Regional Road | 107.632 | \$26,661.35 |
| Resident Rural Gravel | 300.208 | \$19,561.93 |
| Resident Rural Sealed | 209.646 | \$26,218.71 |
| Resident Urban Gravel | 5.303 | \$332.37 |
| Resident Urban Sealed | 100.598 | \$20,909.81 |
| Formed | 6.412 | \$338.00 |
| Vehicular Track | 21.148 | \$727.12 |
| Road Bridge | 0.497 | \$7,032.32 |
| Spoon Drain | 0.083 | \$7.29 |
| Swing Bridge | 0.035 | \$47.25 |
| TOTAL | | \$173,365.90 |

The above infrastructure assets have significant total renewal value estimated at \$173,366,000

1.3 Levels of Service

Our present funding levels are sufficient to continue to provide existing services at current service levels in the medium term.

The Planned Budget should be sufficient to maintain existing service levels for the Transport assets with some gradual improvement in road width and the footpath and kerb and gutter networks.

1.4 Future Demand

The main demands for new services are created by:

- Population Increase will result in increased vehicle movements, increase the need for footpaths and kerb & gutter and roads.
- Increased demand for routes for Restricted Access Vehicles could result in decreased vehicle movements, however, it will result in increased intersection seal damage, increased operational costs evaluating route applications and increased pavement and shoulder damage.
- The aging demographic of our population will result in increased need for footpaths.

These demands will be approached using a combination of managing existing assets, upgrading of existing assets and providing new assets to meet demand. Demand management practices may also include a combination of non-asset solutions, insuring against risks and managing failures.

- Assets for new developments will generally be donated by the developer.

1.5 Lifecycle Management Plan

1.5.1 What does it Cost?

The forecast lifecycle costs necessary to provide the services covered by this AM Plan includes operation, maintenance, renewal, acquisition, and disposal of assets. Although the AM Plan may be prepared for a range of time periods, it typically informs a Long-Term Financial Planning period of 10 years. Therefore, a summary output from the AM Plan is the forecast of 10 year total outlays, which for the Transport assets is estimated as \$46,541,120 or \$4,654,112 on average per year.

1.6 Financial Summary

1.6.1 What we will do

Estimated available funding for the 10 year period is \$58,963,450 or \$5,896,345 on average per year as per the Long-Term Financial plan or Planned Budget. This is 102% of the cost to sustain the current level of service at the lowest lifecycle cost.

The infrastructure reality is that only what is funded in the long-term financial plan can be provided. The Informed decision making depends on the AM Plan emphasising the consequences of Planned Budgets on the service levels provided and risks.

The anticipated Planned Budget for Transport assets gives a excess of \$124,223 on average per year of the forecast lifecycle costs required to provide services in the AM Plan compared with the Planned Budget currently included in the Long-Term Financial Plan. This is shown in the figure below.

Forecast Lifecycle Costs and Planned Budgets




Figure Values are in current dollars.

We plan to provide Transport asset services for the following:

- Operation, maintenance, renewal and upgrade of roads, bridges, carparks, kerb and gutter and footpaths to meet service levels set by this plan and provided for in annual budgets.

1.6.2 What we cannot do

We currently allocate enough budget to sustain these services at the proposed standard, however, we do not allocate sufficient budget to provide all new services being sought or identified as being below adopted service levels. Works and services that cannot be provided under present funding levels are:

- Widening of all bridge structures to the adopted service levels.
- Widening of all roads to the adopted service levels.
- Extension of footpath network to extend identified in the Pedestrian Access and Mobility Plans
- Extension of kerb and gutter network to service all residential streets.
- Upgrading of Lower River Road to provide access to all residences in a 1 in 5 year flood event.

1.6.3 Managing the Risks

Our present budget levels are sufficient to continue to manage risks in the medium term.

The identified risk consequences and treatment plans are captured in Table 6.2: Risks and Treatment Plans.

The main risk consequences are:

- Road Safety is compromised.
- Pedestrian Safety is compromised.
- Street amenity is reduced where open earth drains remain.
- Greater risk of personal and property damage and possible compensation claims against Council.

- Increased maintenance costs where road width is not fit for traffic conditions.

We will endeavor to manage these risks with available funding by:

- Maintaining a high level of inspection of assets and correction of defects
- Improving networks to meet greater level of conformance with adopted service levels

1.7 Asset Management Practices

Our systems to manage assets include:

Council's 'Practical' accounting software and 'AssetFinda' asset management system in conjunction with MapInfo mapping and database.

Assets requiring renewal/replacement are identified from either the asset register or an alternative method. These methods are part of the Lifecycle Model.

- If Asset Register data is used to forecast the renewal costs this is done using the acquisition year and the useful life,
- Alternatively, an estimate of renewal lifecycle costs is projected from external condition modelling systems (such as Pavement Management Systems) and may be supplemented with, or based on, expert knowledge.

The Asset Register was used to forecast the renewal life cycle costs for this Asset Management Plan.

1.8 Monitoring and Improvement Program

The next steps resulting from this AM Plan to improve asset management practices are:

- Condition rating of Assets
- Review remaining life of assets
- Componentisation of assets such as drainage structures, signs and traffic facilities including review of unit costs
- Develop chart of accounts to allow separation of operation costs and maintenance costs and to split the maintenance costs into reactive, planned and cyclic and to separate capital expenditure into renewal, new and upgrade works.
- Investigate options to integrate Asset Management system with the Accounting / financial system
- Review customer request /complaint settings in customer request management system to reflect desirable data being collected
- Ensure all assets in Asset Management System have a condition score

2.0 Introduction

2.1 Background

This Asset Management Plan communicates the requirements for the sustainable delivery of services through management of assets, compliance with regulatory requirements, and required funding to provide the appropriate levels of service over the long term planning period.

The asset management plan is to be read with the Berrigan Shire Council's Asset Management Policy (2020), and the following associated planning documents:

- Berrigan Shire 2023
- Berrigan Shire Council Asset Accounting Policy 2019
- Engagement Framework 2011
- Resourcing Strategy 2013-2023 (includes Asset Management Strategy and LTFP)
- Delivery Program 2020-2024
- Liveability and Healthy Ageing Strategy Action Plan 2013-2017
- Berrigan Pedestrian and Mobility Plan 2020
- Barooga Pedestrian and Mobility Plan 2020
- Finley Pedestrian and Mobility Plan 2020
- Tocumwal Pedestrian and Mobility Plan 2020

Berrigan Shire Council is well advanced in Asset Management practices. This is the fourth version of asset management plans prepared for these assets using the NAMS process with the initial plan being developed in 2009. All plans have been developed by Council staff and processes have been set up for inspection and management of assets along with long term financial planning to ensure the assets are maintained and improved to satisfy adopted service levels.

The infrastructure assets covered by this Asset Management Plan include roads, bridges, carparks, kerb and gutter and footpaths. For a detailed summary of the assets covered in this Asset Management Plan refer to Table 5.1.1 in Section 5.

These assets are used to provide an adequate transport network to be used by road transport, motor vehicles, bicycles, pedestrians and people using mobility aids.


The infrastructure assets included in this plan have a total replacement value of **\$173,365,905**

Key stakeholders in the preparation and implementation of this Asset Management Plan are shown in Table 2.1.

Table 2.1: Key Stakeholders in the AM Plan

| Key Stakeholder | Role in Asset Management Plan |
|--|---|
| Shire Councillors | <ul style="list-style-type: none"> • Represent needs of community/shareholders, • Allocate resources to meet the organisation's objectives in providing services while managing risks, • Ensure organisation is financial sustainable. |
| State Local Member | <ul style="list-style-type: none"> • Represent community interest |
| Transport NSW | <ul style="list-style-type: none"> • State department responsible for management of Federal and State Highways and Murray River Crossings and traffic facilities on all roads. • Has control of works carried out by Council on Regional Roads and provides funding for works on these roads. |
| Murray Irrigation | <ul style="list-style-type: none"> • CAAT agreement for maintenance and improvement of bridges and culverts conveying irrigation water across roads. • Interest in drainage from roads and streets |
| West Corugan Private Irrigation District | <ul style="list-style-type: none"> • Interest in drainage from roads and streets • Interest in irrigation bridges and culverts |
| Local Land Services | <ul style="list-style-type: none"> • Coordinate management strategies within the Murray Catchment for the sustainable use of its natural resources and protection of native vegetation. • Travelling Stock Routes • Vegetation |
| The General Public | <ul style="list-style-type: none"> • Road network that provides reliable and safe transport connectivity between homes, commercial centres, employment locations and recreation locations. |
| Local Businesses | <ul style="list-style-type: none"> • Road network adequate to transfer freight throughout the shire. • Road network adequate for customers to access their businesses and for freight transfers to and from. |
| National Heavy Vehicle Regulator | <ul style="list-style-type: none"> • Road network adequate for restricted access vehicles • Road network to have designated freight networks. |
| NSW Department of Infrastructure | <ul style="list-style-type: none"> • Funding organisation for grants for roadworks. |

Our organisational structure for service delivery from infrastructure assets is detailed below,



2.2 Goals and Objectives of Asset Ownership

Our goal in managing infrastructure assets is to meet the defined level of service (as amended from time to time) in the most cost effective manner for present and future consumers. The key elements of infrastructure asset management are:

- Providing a defined level of service and monitoring performance,
- Managing the impact of growth through demand management and infrastructure investment,
- Taking a lifecycle approach to developing cost-effective management strategies for the long-term that meet the defined level of service,
- Identifying, assessing and appropriately controlling risks, and
- Linking to a Long-Term Financial Plan which identifies required, affordable forecast costs and how it will be allocated.

Key elements of the planning framework are

- Levels of service – specifies the services and levels of service to be provided,
- Future demand – how this will impact on future service delivery and how this is to be met,
- Lifecycle management – how to manage its existing and future assets to provide defined levels of service,
- Financial summary – what funds are required to provide the defined services,
- Asset management practices – how we manage provision of the services,
- Monitoring – how the plan will be monitored to ensure objectives are met,
- Asset management improvement plan – how we increase asset management maturity.

Other references to the benefits, fundamentals principles and objectives of asset management are:

- International Infrastructure Management Manual 2015 ¹
- ISO 55000²


A road map for preparing an Asset Management Plan is shown below.

Road Map for preparing an Asset Management Plan

Source: IPWEA, 2006, IIMM, Fig 1.5.1, p 1.11

¹ Based on IPWEA 2015 IIMM, Sec 2.1.3, p 2 | 13

² ISO 55000 Overview, principles and terminology



2.3 Community Consultation

This asset management plan includes community comments and feedback on service levels and the condition of the Council's transport network prior to adoption by the Council. This revision of the asset management plan will assist the Council and the community match the level of service needed by the community, service risks and the benefits with our community's ability and willingness to pay for the service.

3.0 LEVELS OF SERVICE

3.1 Customer Research and Expectations

The last review of this asset management (2014) was conducted in conjunction with the Council's review of its Pedestrian Access and Mobility Plans (Barooga, Berrigan, Finley and Tocumwal). This consultation and engagement process included town-based street meetings. At these meetings Shire residents were given information on Council's 10-year program of works with resident feedback sought on the proposed service levels. Comment, at these meetings, was also sought on what works also needs be prioritised.

Since this March 2014 program of engagement the key messages which inform the Council's Transport Asset Management Plan 2014 – 2019 and the Council's Pedestrian Access and Mobility Plans and this review of these plans remains unchanged. These messages are that the Council's Transport Asset Plan and Pedestrian Access and Mobility Plan (PAMP) must:

1. Ensure that the asset management of our Roads, Streets and Bridges is financially sustainable.
2. Meet legislative requirements for asset management and pedestrian access and mobility
3. Ensure Council decision-making on the management of Roads, Bridges, Footpaths, Kerb and Guttering is informed by community consultation, feedback from other stakeholders and road users.
4. Ensure that Council has the resources and operational capabilities it needs over the life of its Transport Asset Management Plan to meet the service levels identified in the asset management plan and PAMP.

Engagement Program 2014 - 2020

The Council, per its [Community Engagement Framework](#), is committed to a rolling program of engagement with Council residents, other stakeholders and service users. The Council's transport and PAMP network contributes to the social and economic fabric of our communities therefore, as part of the Council's rolling program of community engagement in the development of its Town Landscape Management Plan's (2014 – 2018), Precinct Landscape Management Plan's ([Tocumwal Foreshore Master Plan 2016](#), [Barooga Foreshore Master Plan 2016](#), [Finley Railway Park Master Plan 2018](#), Hayes and Apex Park – Berrigan Master Plans 2019), also the 2016 review of the Council's [Community Strategic Plan 2027](#) and the 2018 review of the Berrigan Shire Council [Liveability and Disability Action Plan 2017 – 2021](#) a comprehensive program of community engagement which is documented in these plans has informed the development and adoption by the Council of these plans.

The Council's [Town Landscape Management Plans](#) include actions about the 'walkability' of our pedestrian access, the separation of road uses: access for local traffic, parking and opportunities for the resolution of heavy vehicle parking and other long vehicle parking in our urban areas. The precinct landscape plans provide detailed information on service levels and expectations for active transport in particular the connectivity of routes, also service levels for local access and parking requirements. The Council's review of its Community Strategic Plan 2016 provided residents, visitors and local business with further opportunities to comment on the connectivity and service levels and priorities with the maintenance of existing transport network, pedestrian access and trails between our towns identified as central to strengthening the liveability of our towns. This theme was expanded by community feedback in the development of the Council's Liveability and Disability Action Plan 2017 with community feedback highlighting the need to continue the Council's investment in improving pedestrian access and parking.

Specific feedback on service users expectations and experience of the Council's transport infrastructure network was also sought from community members as part of the Berrigan Shire Council's Residents and Business Satisfaction Survey 2015. This statistically valid survey was conducted by Nexus Research Pty Ltd. This 2015 survey confirmed that current levels of service be maintained. Overall, there were no comments received suggesting an increase in current service levels i.e.: gravel roads upgraded to sealed etc.

Specific comments drawn from the Council's rolling program of community engagement includes the need to investigate and where possible address the following:

- The intersection of Vermont Street, Golf Course Road and Collie Street, Barooga
 - The intersection of Murray Street and Pinnuck Street, Finley safety for pedestrians Murray Street – NSW Transport controlled road
 - Long vehicle parking in Finley – adjacent to or near Murray Street, retail precinct
 - Heavy vehicle parking in Berrigan – opposite Hayes Park, Jerilderie Street, Berrigan
-

- Heavy vehicle and long vehicle parking in Tocumwal – Dean Street, Tocumwal and also various locations within Tocumwal
- Pedestrian access to Finley Hospital and Finley Regional Care – Dawe Avenue, Finley – condition of parking bays Dawe Avenue, Finley
- Safety of angle parking for disabled parking bays Jerilderie Street, Tocumwal and Murray Street, Finley
- Connectivity – footpaths and signage from off street car parking areas and Finley's railway park
- The camber and undulation of the footpath network in various locations

During the course of the development of the Town Landscape Plans no substantive comments were received requesting a change to overall service levels for footpaths and kerb and guttering. Observations, as has been the case previously, were made by some property owners that they would like the footpath network extended to their side of the street. There is, however, limited support from property owners for the installation of a footpath if the NSW the property owner is required to pay a contribution toward the path's installation. Comments continue to be received in relation to weed management – in particular the control of Bindi and the difficulty this caused for property owners.

3.2 Strategic and Corporate Goals

This asset management plan is prepared under the direction of Berrigan Shire Council's vision, mission, goals and objectives.

Our vision is:

In 2027 we will be recognised as a Shire that builds on and promotes our natural assets and advantages to create employment and economic activity to attract residents, families and tourists.

Relevant organisation goals and objectives and how these are addressed in this asset management plan are:

Table 3.2: Organisation Goals and how these are addressed in this Plan

| Outcome | Objective | How Goal and Objectives are addressed in AM Plan |
|--|---|--|
| Sustainable and Natural Built Landscapes | Support sustainable use of our natural resources and built landscape | Ensuring that Council's services and infrastructure are provided in a sustainable manner, with the appropriate levels of service to residents, visitors and the environment. (Asset Management Strategy 2019) |
| | Connect and protect our communities | |
| Good Government | Ensure effective governance by Council of Council operations and reporting | Establishing processes that integrate asset management and community strategic planning with Council corporate and long-term financial planning. Creating an environment where all Council employees take an integral part in overall management of Council assets by creating and sustaining asset management awareness throughout the Council. Meeting legislative requirements for asset management. Ensuring resources and operational capabilities are identified and responsibility for asset management is allocated. Demonstrating transparent and responsible asset management processes that align with demonstrated best practice. (Asset Management Strategy 2019) |
| Supported and Engaged Communities | Create safe, friendly and accessible communities | Safe paths and travel in and between our towns. Age friendly pedestrian access in and between open space, public buildings and retail centres (Liveability and Healthy Ageing Strategy 2017-2021) |
| | Support community engagement through life-long learning, culture and recreation | |
| Diverse and Resilient | Strengthen and diversify the local economy | Develop and promote Berrigan Shire regional transport and freight infrastructure. (Economic Development Strategy 2019-2023) |
| | Connect local, regional and national road, rail and aviation infrastructure | |

The Council will exercise its duty of care to ensure public safety in accordance with the infrastructure risk management plan prepared in conjunction with this AM Plan. Management of infrastructure risks is covered in Section 5.2

3.3 Legislative Requirements

There are many legislative requirements relating to the management of assets. Legislative requirements that impact the delivery of the Transport service are outlined in Table 3.3.

Table 3.3: Legislative Requirements

| Legislation | Requirement |
|---|---|
| Local Government Act 1993 No 30 | Sets out role, purpose, responsibilities and powers of local governments including the preparation of a long term financial plan supported by asset management plans for sustainable service delivery. |
| Environmental Planning and Assessment Act 1979 No 203 | Requirement for Local Environmental Plans and Development Control Plans. Provides for Council control of development of towns and approval of infrastructure expansion. |
| Local Land Services Act 2013 No 51 | Requirement for ongoing management plan. Promotes the coordination of activities within catchment areas. Under the provision of this Act, Local Catchment Management Authorities oversee this process in the region. Also oversee travelling stock routes |
| Soil Conservation Act 1938 No 10 | Preservation of water course environment. |
| Work Health and Safety Act 2011 No 10 | Impacts all operations in relation to safety of workers and the public. Council's responsibility to ensure health, safety and welfare of employees and others at places of work. |
| Roads Act 1993 No 33 | Provides authority to Council for administration and development of roads and streets |
| Road Transport Act 2013 No 18 | Sets requirements for vehicles and operators using roads. |
| Transport Administration Act 1988 No 109 | Provides authority to Roads and Traffic Authority for management of roads. |
| Australian Road Rules | Sets requirements for vehicles and operators using roads. |
| Heavy Vehicle (Adoption of National Law) Act 2013 No 42 Heavy Vehicle National Law Act 2013 No 42a | Establishes a national scheme for facilitating and regulating the use of heavy vehicles on roads in a way that-- (a) promotes public safety; and (b) manages the impact of heavy vehicles on the environment, road infrastructure and public amenity; and (c) promotes industry productivity and efficiency in the road transport of goods and passengers by heavy vehicles; and (d) encourages and promotes productive, efficient, innovative and safe business practices. |

3.4 Customer Values

Service levels are defined in three ways, customer values, customer levels of service and technical levels of service.

Customer Values indicate:

- what aspects of the service is important to the customer,
- whether they see value in what is currently provided and
- the likely trend over time based on the current budget provision

Table 3.4: Customer Values

| Service Objective: | | | |
|--|---|--|--|
| Customer Values | Customer Satisfaction Measure | Current Feedback | Expected Trend Based on Planned Budget |
| To be able to drive/ride on roads and streets that are safe and functional. | Customer Requests received and periodic community consultation. | Customers are reasonably happy with the current level of service. | Council budgets for continual improvement of the road network and therefore it is expected that the trend will be greater satisfaction |
| To be able to walk on footpaths and tracks that are safe and functional. | Customer Requests received and periodic community consultation. | Customers are reasonably happy with the current level of service. | Council budgets for continual improvement of the road network and therefore it is expected that the trend will be greater satisfaction |
| To have kerb and gutter in urban areas that is safe and functional and enhances the amenity of the neighbourhood | Customer Requests received and periodic community consultation. | There are current issues with damaged/deformed gutters and unserviced areas. | Council budgets for continual improvement of the road network and therefore it is expected that the trend will be greater satisfaction |

3.5 Customer Levels of Service

The Customer Levels of Service are considered in terms of:

Quality How good is the service ... what is the condition or quality of the service?

Function Is it suitable for its intended purpose Is it the right service?

Capacity/Use Is the service over or under used ... do we need more or less of these assets?

In Tables 3.5.1 to 3.5.4 under each of the service measures types (Quality, Function, Capacity/Use) there is a summary of the performance measure being used, the current performance, and the expected performance based on the current funding level.

These are measures of fact related to the service delivery outcome e.g. number of occasions when service is not available, condition %'s of Very Poor, Poor/Average/Good, Very Good and provide a balance in comparison to the customer perception that may be more subjective.

Table 3.5.1: Sealed Roads Customer Level of Service Measures

| Type of Measure | Level of Service | Performance Measure | Current Performance | Expected Trend Based on Planned Budget |
|------------------|-----------------------------|---------------------|---------------------|--|
| Condition | Rideability | Customer Requests | 8 | Expected to trend down |
| | Visibility | Customer Requests | 2 | |
| | Confidence levels | | Medium | Medium |
| Function | Meet user requirements for: | Customer Requests | | Expected to trend down |
| | • Accessibility | | 1 | |
| | • Road width | | 1 | |
| | • Traffic management | | 1 | |
| | Confidence levels | | Medium | Medium |
| Safety | Safe, accessible network | Accident Reports | 1 | Expected to trend down |
| | | Customer Requests | 1 | |
| | Confidence levels | | Medium | Medium |

Table 3.5.2: Unsealed Roads Customer Level of Service Measures

| Type of Measure | Level of Service | Performance Measure | Current Performance | Expected Trend Based on Planned Budget |
|------------------|-----------------------------|---------------------|---------------------|--|
| Condition | Rideability | Customer Requests | 17 | Expected to trend down |
| | Visibility | Customer Requests | 1 | |
| | Confidence levels | | Medium | Medium |
| Function | Meet user requirements for: | Customer Requests | | Expected to trend down |
| | • Accessibility | | 4 | |
| | • Road width | | 1 | |
| | • Traffic Management | | 29 | |
| | Confidence levels | | Medium | Medium |
| Safety | Safe, accessible network | Accident Reports | 0 | Expected to remain the same |
| | | Customer Requests | 14 | Expected to trend down |
| | Confidence levels | | Medium | Medium |

Table 3.5.3: Footpaths Customer Level of Service Measures

| Type of Measure | Level of Service | Performance Measure | Current Performance | Expected Trend Based on Planned Budget |
|------------------|-----------------------------|---------------------|---------------------|--|
| Condition | Surface | Customer Requests | 14 | Expected to trend down |
| | Lighting | Customer Requests | 1 | |
| | Confidence levels | | Medium | Medium |
| Function | Meet user requirements for: | Customer Requests | | Expected to remain the same |
| | • Accessibility | | 1 | |
| | • Location | | 0 | |
| | | | | |
| | Confidence levels | | Medium | Medium |
| Safety | Safe, accessible network | Incident Reports | 11 | Expected to trend down |
| | | Customer Requests | 6 | |
| | Confidence levels | | Medium | Medium |

Table 3.5.4: Kerb & Gutter Customer Level of Service Measures

| Type of Measure | Level of Service | Performance Measure | Current Performance | Expected Trend Based on Planned Budget |
|------------------|---|---------------------|---------------------|--|
| Condition | Flooding/Amenity | Customer Requests | 4 | Expected to trend down |
| | Confidence levels | | Medium | Medium |
| Function | Meet user requirements for: <ul style="list-style-type: none"> • Accessibility • Location | Customer Requests | 0 0 | Expected to remain the same |
| | Confidence levels | | Medium | Medium |
| Safety | Damage | Customer Requests | 9 | Expected to trend down |
| | Confidence levels | | Medium | Medium |

3.6 Technical Levels of Service

Technical Levels of Service – To deliver the customer values, and impact the achieved Customer Levels of Service, are operational or technical measures of performance. These technical measures relate to the activities and allocation of resources to best achieve the desired customer outcomes and demonstrate effective performance.

Technical service measures are linked to the activities and annual budgets covering:

- **Acquisition** – the activities to provide a higher level of service (e.g. widening a road, sealing an unsealed road, replacing a pipeline with a larger size) or a new service that did not exist previously (e.g. a new library).
- **Operation** – the regular activities to provide services (e.g. opening hours, cleansing, mowing grass, energy, inspections, etc).
- **Maintenance** – the activities necessary to retain an asset as near as practicable to an appropriate service condition. Maintenance activities enable an asset to provide service for its planned life (e.g. road patching, unsealed road grading, building and structure repairs),
- **Renewal** – the activities that return the service capability of an asset up to that which it had originally provided (e.g. road resurfacing and pavement reconstruction, pipeline replacement and building component replacement),

Service and asset managers plan, implement and control technical service levels to influence the service outcomes.³

³ IPWEA, 2015, IIMM, p 2|28.

3.6.1 Adopted Levels of Service Road Width and Clearzones

The following tables 3.6.a to 3.6.c set out the adopted desirable standards for road width and clearzone distance.

| Table 3.6.a - Road Hierarchy | | | | | | | | | |
|------------------------------|----------------------------------|--|---------------------|-------------|------------------|------------------|--------------------|----------|------------------|
| Road Classification No. | Road Classification | Standard | Pavement/Seal Width | Lane Width | Typical Warrants | | | | |
| | | | | | Traffic Counts | % Heavy Vehicles | No. of Homes/Km | Mail Run | School Buses/Day |
| | Highways (RTA Determined) | | | | | | | | |
| 1 | Regional Roads | Seal | 8.0m | 3.5m | >300 AADT | n/a | n/a | n/a | n/a |
| 2 | Arterial Roads | Seal | 8.0m | 3.5m | >300 AADT | >20% | n/a | n/a | n/a |
| 3 | Collector Roads | Seal | 7.5m | 3.25m | >80 AADT | >20% | >3 homes/km | >1 | >1 |
| | Collector Roads | Gravel | 6.5m | 3.25m | <80 AADT | | | | |
| 4 | Residential Access | Seal | 6.2m | 3.1m | >80 AADT | >20% | >3 homes/km | >1 | >1 |
| | Residential Access | Gravel | 6.2m | 3.1m | <80 AADT | | 1 or more homes/km | | |
| 5 | Property Access | Seal | 6.2m | 3.1m | >80 AADT | >30% | No homes | | |
| | Property Access | Gravel | 5.0m | Shared 3.5m | <80>10 AADT | >20% | No homes | | |
| | Property Access | Formed | 5.0m | Shared 3.5m | <10 AADT | | No homes | | |
| | Property Access | Unformed | n/a | | <1 AADT | | No homes | | |
| NOTES: | | | | | | | | | |
| | | 1. For a road to be considered for upgrading from formed to gravel or gravel to seal it must meet traffic count warrants plus 1 of the other 4 warrants. | | | | | | | |
| | | 2. Priority for works will be given to roads meeting the most warrants. | | | | | | | |
| | | 3. Urban streets construction standards determined on an individual basis depending on site conditions, traffic and in accordance with the Council's Subdivision Code. | | | | | | | |

Clear Zones

Berrigan Shire Council adopted the Roadside Hazard Treatment Policy (Jan 2012). This policy set desired lane widths and these have been subjected to minor amendments to suit current conditions. They are set out in Table 3.6.b and clear zones in Table 3.6.c below and the Roadside Hazard Treatment Policy should be amended accordingly.

| Table 3.6.b | | |
|--------------------------|-------------------|-----------------------|
| Road Classification | Design AADT (vpd) | Design Lane Width (m) |
| Sealed Roads | | |
| Regional Roads | 1500 | 3.5 |
| Arterial Roads | 800 | 3.5 |
| Collector Roads | 300 | 3.25 |
| Residential Access | 200 | 3.1 |
| Property Access | 200 | 3.1 |
| Unsealed Roads | | |
| Collector Roads | 100 | 3.25 |
| Residential Access Roads | 100 | 3.1 |
| Property Access Roads | 100 | Shared 3.5 |

| Table 3.6.c | | | | |
|--------------------------|-------------------|-----------------------|------------------------|-------------------------------------|
| Road Classification | Design AADT (vpd) | Design Lane Width (m) | Minimum Clear Zone (m) | Minimum Clear Zone + Lane Width (m) |
| Sealed Roads | | | | |
| Regional Roads | 1500 | 3.5 | 5.0 | 8.5 |
| Arterial Roads | 800 | 3.5 | 5.0 | 8.5 |
| Collector Roads | 300 | 3.25 | 3.0 | 6.25 |
| Residential Access | 200 | 3.1 | 2.0 | 5.1 |
| Property Access | 200 | 3.1 | 2.0 | 5.1 |
| Unsealed Roads | | | | |
| Collector Roads | 100 | 3.1 | 2.0 | 5.1 |
| Residential Access Roads | 100 | 3.1 | 2.0 | 5.1 |
| Property Access Roads | 100 | Shared 3.5 | 2.75 | 4.5 |

Tables 3.6.1 to 3.6.4 show the activities expected to be provided under the current Planned Budget allocation, and the Forecast activity requirements being recommended in this AM Plan.

Table 3.6.1: Sealed Roads Technical Levels of Service

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|------------------------------------|---|---|----------------------|----------------------------|
| TECHNICAL LEVELS OF SERVICE | | | | |
| Acquisition | Widen roads to meet adopted standards for road classification | Percentage of road network complying | 46% | 100% |
| | Upgrade pavements to meet current loading requirements | Percentage of road network in poor condition due to inadequate pavement | 6% | 0% |

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|--------------------|--|--|----------------------|----------------------------|
| | Replace/Upgrade Bridges to meet adopted standards | Percentage of bridges complying | 60% | 100% |
| | Reseal roads within adopted lifecycle time for road classification | Percentage of seal network complying | 95% | 100% |
| | Accept gifted roads for new developments | Roads accepted are constructed to adopted standards | 100% | 100% |
| | | Budget | \$322,775 | \$322,775 |
| Operation | Ensure road network is managed and developed in a sustainable manner | AMP Reviewed and Updated on time Adopted inspection and reporting timelines adhered to NHVR applications responded to within timeline Council reporting on budget and achievement completed on time Environmental requirements are complied with. Design, Supervision and Contract Management are provided in a professional manner | Compliant | Compliant |
| | | Budget | \$792,950 | \$792,950 |
| Maintenance | To maintain the sealed road network including bridges and drainage structures in a safe and functional state | Adopted inspections intervals and response times achieved | 60% compliance | 100% compliance |
| | | Budget | \$1,493,922 | \$1,493,922 |
| Renewal | To reconstruct and reseal segments of the sealed road network before they become unserviceable | Condition Rating Useful life | 100% serviceable | 100% serviceable |
| | To reconstruct bridges and drainage structures before they | Condition Rating Useful life | 100% serviceable | 100% serviceable |

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|--------------------|---|---|----------------------|----------------------------|
| | become unserviceable | | | |
| | | Budget | \$1, 790,725 | \$2,558,677 |
| Disposal | Dispose of sealed road pavements and seals that are being renewed prior to the end of the adopted useful life | Asset inventory and data maintained to be current at the end of financial year. | Comply | Comply |
| | Dispose of sealed road pavements and seals that are no longer required due to realignment | Asset inventory and data maintained to be current at the end of financial year. | Comply | Comply |
| | Dispose of bridges and drainage structures that are being renewed prior to the end of the adopted useful life | Asset inventory and data maintained to be current at the end of financial year. | | |
| | | Budget | <i>Nil</i> | <i>Nil</i> |

Table 3.6.2: Unsealed Roads Technical Levels of Service

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|------------------------------------|--|---|---|----------------------------|
| TECHNICAL LEVELS OF SERVICE | | | | |
| Acquisition | Widen roads to meet adopted standards for road classification | Percentage of road network complying | 6% | 100% |
| | Upgrade pavements to meet current loading requirements | Percentage of road network in poor condition due to inadequate pavement | 5% | 0% |
| | Replace/Upgrade Bridges to meet adopted standards | Percentage of bridges complying | 0% on bridge width | 100% |
| | | | | |
| | | Budget | <i>Nil</i> | <i>Nil</i> |
| Operation | Ensure road network is managed and developed in a sustainable manner | AMP Reviewed and Updated on time Adopted inspection and reporting timelines adhered to | Non compliance with AMP review time and some Maintenance Response Times | Full Compliance |

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|--------------------|--|---|----------------------|----------------------------|
| | | NHVR applications responded to within timeline Council reporting on budget and achievement completed on time Environmental requirements are complied with. Design, Supervision and Contract Management are provided in a professional manner | | |
| | | Budget | <i>\$400,000</i> | <i>\$400,000</i> |
| Maintenance | To maintain the unsealed road network including bridges and drainage structures in a safe and functional state | Adopted inspections intervals and response times achieved | 100% compliance | 100% compliance |
| | | Budget | \$1,087,848 | \$1,087,848 |
| Renewal | To reconstruct segments of the unsealed road network before they become unserviceable | Condition Rating Useful life | 100% serviceable | 100% serviceable |
| | To reconstruct bridges and drainage structures before they become unserviceable | Condition Rating Useful life | 100% serviceable | 100% serviceable |
| | | Budget | <i>Nil</i> | <i>Nil</i> |
| Disposal | Dispose of unsealed road pavements that are being renewed prior to the end of the adopted useful life | Asset inventory and data maintained to be current at the end of financial year. | Comply | Comply |
| | Dispose of unsealed road pavements that are no longer required due to realignment | Asset inventory and data maintained to be current at the end of financial year. | Comply | Comply |
| | Dispose of bridges and drainage structures that are | Asset inventory and data maintained to be | | |

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|--------------------|---|---------------------------------------|----------------------|----------------------------|
| | being renewed prior to the end of the adopted useful life | current at the end of financial year. | | |
| | | Budget | <i>Nil</i> | <i>Nil</i> |

Table 3.6.3: Footpaths Technical Levels of Service

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|------------------------------------|--|--|---|----------------------------|
| TECHNICAL LEVELS OF SERVICE | | | | |
| Acquisition | Extend footpath network to areas adopted in the Pedestrian Access and Mobility Plans for each town | Percentage of footpath network constructed | 78% | 100% |
| | Widen existing footpath to meet current standards | Percentage of footpath network complying | 100% | 100% |
| | Accept gifted footpaths for new developments | Footpaths accepted are constructed to adopted standards | 100% | 100% |
| | | | | |
| | | Budget | <i>\$58,000</i> | <i>\$168,000</i> |
| Operation | Ensure footpath network is managed and developed in a sustainable manner | AMP Reviewed and Updated on time Adopted inspection and reporting timelines adhered to Council reporting on budget and achievement completed on time Environmental requirements are complied with. Design, Supervision and Contract Management are provided in a professional manner | Non compliance with AMP review time and some Maintenance Response Times | Full Compliance |
| | | Budget | <i>\$25,000</i> | <i>\$25,000</i> |
| Maintenance | To maintain the footpath network in a safe and functional state | Adopted inspections intervals and response times achieved | 50% compliance | 100% compliance |
| | | Budget | <i>\$20,306</i> | <i>\$20,306</i> |
| Renewal | To reconstruct segments of the | Condition Rating | 100% serviceable | 100% serviceable |

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|--------------------|---|---|----------------------|----------------------------|
| | footpath network before they become unserviceable | Useful life | | |
| | | Budget | \$35,000 | \$15,220 |
| Disposal | Dispose of footpaths that are being renewed prior to the end of the adopted useful life | Asset inventory and data maintained to be current at the end of financial year. | Comply | Comply |
| | Dispose of footpaths that are no longer required due to realignment | Asset inventory and data maintained to be current at the end of financial year. | Comply | Comply |
| | | Budget | Nil | Nil |

Table 3.6.4: Kerb & Gutter Technical Levels of Service

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|------------------------------------|---|--|--|----------------------------|
| TECHNICAL LEVELS OF SERVICE | | | | |
| Acquisition | Extend Kerb and Gutter network to service developed urban areas | Percentage of developed urban area serviced | 86% | 100% |
| | Accept gifted kerb and gutter for new developments | Kerb and gutter accepted is constructed to adopted standards | 100% | 100% |
| | | | | |
| | | | | |
| | | Budget | \$101,200 | \$101,200 |
| Operation | Ensure kerb and gutter network is managed and developed in a sustainable manner | AMP Reviewed and Updated on time Adopted inspection and reporting timelines adhered to Council reporting on budget and achievement completed on time Environmental requirements are complied with. Design, Supervision and Contract Management are provided in a | Non compliance with AMP review time and Maintenance Response Times | Full Compliance |

| Lifecycle Activity | Purpose of Activity | Activity Measure | Current Performance* | Recommended Performance ** |
|--------------------|--|---|---|----------------------------|
| | | professional manner | | |
| | | Budget | \$25,000 | \$25,000 |
| Maintenance | To maintain the kerb and gutter network in a safe and functional state | Adopted inspections intervals and response times achieved | Non Compliance | Full Compliance |
| | | Budget | \$16,020 | \$16,400 |
| Renewal | To reconstruct segments of the kerb and gutter network before they become unserviceable | Condition Rating Useful life | Periodic replacement of segments that have been identified as having rotated and are holding puddles of water or creating trip hazards. | 100% serviceable |
| | | Budget | \$130,500 | \$6,886 |
| Disposal | Dispose of kerb and gutter that is being renewed prior to the end of the adopted useful life | Asset inventory and data maintained to be current at the end of financial year. | Comply | Comply |
| | Dispose of kerb and gutter that is no longer required due to realignment | Asset inventory and data maintained to be current at the end of financial year. | Comply | Comply |
| | | Budget | Nil | Nil |

Note: * Current activities related to Planned Budget.

** Forecast required performance related to forecast lifecycle costs.

It is important to monitor the service levels provided regularly as these will change. The current performance is influenced by work efficiencies and technology, and customer priorities will change over time.

4.0 FUTURE DEMAND

4.1 Demand Drivers

Drivers affecting demand include things such as population change, regulations, changes in demographics, seasonal factors, vehicle ownership rates, consumer preferences and expectations, technological changes, economic factors, agricultural practices, environmental awareness, etc.

4.2 Demand Forecasts

The present position and projections for demand drivers that may impact future service delivery and use of assets have been identified and documented.

4.3 Demand Impact and Demand Management Plan

The impact of demand drivers that may affect future service delivery and use of assets are shown in Table 4.3.

Demand for new services will be managed through a combination of managing existing assets, upgrading of existing assets and providing new assets to meet demand and demand management. Demand management practices can include non-asset solutions, insuring against risks and managing failures.

Opportunities identified to date for demand management are shown in Table 4.3. Further opportunities will be developed in future revisions of this Asset Management Plan.

Table 4.3: Demand Management Plan

| Demand driver | Current position | Projection | Impact on services | Demand Management Plan |
|----------------------------|--|--|---|---|
| Population | 8510 | 9688 | Increased vehicle movements. Increase need for footpaths and kerb & gutter and roads | Assets for new developments will generally be donated by the developer. Kerb and gutter extensions will be provided on a priority basis and within capital budget constraints. Footpath network extensions will be provided generally in accordance with the adopted PAMP priorities and within capital budget constraints. |
| Restricted Access Vehicles | Standard Vehicles/Road Trains | B-Triples. AB-Triples and Higher Mass Limits | Decreased vehicle movements. Increased intersection seal damage. Increased route applications. Increase pavement damage | The rural road network will be continually upgraded generally in accordance with priorities set out in this plan and within capital budget constraints. |
| Demographics | Average age of population greater than State average | Will become even greater | Increased need for footpaths | Footpath network extensions will be provided generally in accordance with the adopted PAMP priorities and within capital budget constraints. |

4.4 Asset Programs to meet Demand

The new assets required to meet demand may be acquired, donated or constructed. Additional assets are discussed in Section 5.4.

Acquiring new assets will commit the Berrigan Shire Council to ongoing operations, maintenance and renewal costs for the period that the service provided from the assets is required. These future costs are identified and considered in developing forecasts of future operations, maintenance and renewal costs for inclusion in the long-term financial plan (Refer to Section 5).

4.5 Climate Change and Adaption

The impacts of climate change can have a significant impact on the assets we manage and the services they provide. In the context of the Asset Management Planning process climate change can be considered as both a future demand and a risk.

How climate change will impact on assets can vary significantly depending on the location and the type of services provided, as will the way in which we respond and manage those impacts.

As a minimum we should consider both how to manage our existing assets given the potential climate change impacts, and then also how to create resilience to climate change in any new works or acquisitions.

Opportunities identified to date for management of climate change impacts on existing assets are shown in Table 4.5.1

Table 4.5.1 Managing the Impact of Climate Change on Assets

| Climate Change Description | Projected Change | Potential Impact on Assets and Services | Management |
|--|---|---|---|
| Lower River Road, Taylors Road, Bullatale Road | Road will become impassable and damaged due to flooding more frequently | More frequent damage to roads and structures due to flooding. More frequent interruptions to access to properties | Increase level of causeways to provide uninterrupted access for 1 in 5 year design flood. |

Additionally, the way in which we construct new assets should recognise that there is opportunity to build in resilience to climate change impacts. Buildings resilience will have benefits:

- Assets will withstand the impacts of climate change
- Services can be sustained
- Assets that can endure may potentially lower the lifecycle cost and reduce their carbon footprint

Table 4.5.2 summarises some asset climate change resilience opportunities.

Table 4.5.2 Building Asset Resilience to Climate Change

| New Asset Description | Climate Change impact These assets? | Build Resilience in New Works |
|---|---|---|
| Upgrade Lower River Road, Taylors Road and Bullatale Road to provide uninterrupted access to all dwellings for 1 in 5 year design flood | Access to properties will be available for 99% of time. | Road constructed with structures that allow 1 in 10 year flood flows only over/through protected structures. Water depth for 1 in 5 year flow over causeways to be maximum 200mm deep. |

The impact of climate change on assets is a new and complex discussion and further opportunities will be developed in future revisions of this Asset Management Plan.

5.0 LIFECYCLE MANAGEMENT PLAN

The lifecycle management plan details how the Berrigan Shire Council plans to manage and operate the assets at the agreed levels of service (Refer to Section 3) while managing life cycle costs.

5.1 Background Data

5.1.1 Physical parameters

The assets covered by this Asset Management Plan are shown in Table 5.1.1.

They include roads, bridges, carparks, kerb and gutter and footpaths.

These assets are used to provide an adequate transport network to be used by road transport, motor vehicles, bicycles, pedestrians and people using mobility aids.

The age profile of the assets included in this AM Plan are shown in Figure 5.1.1.


Table 5.1.1: Assets covered by this Plan

| Asset category | Dimension (km) | Replacement Value (\$000) |
|------------------------------|----------------|---------------------------|
| Arterial Road | 9.924 | \$4,340.10 |
| Asphalt Footpath | 7.680 | \$358.98 |
| Asphalted Concrete Footpath | 1.502 | \$599.56 |
| Barrier Kerb and Gutter | 62.36 | \$6,610.12 |
| Brick Kerb and Gutter | 0.196 | \$20.77 |
| Carpark | 0.340 | \$272.65 |
| Collector Gravel Road | 17.533 | \$1,235.06 |
| Collector Sealed Road | 158.905 | \$27,936.90 |
| Concrete Footpath | 24.094 | \$ 3,021.88 |
| Firetrail | 37.915 | \$2,036.76 |
| Gravel Footpath | 2.983 | \$53.72 |
| Kerb Only | 5.539 | \$587.18 |
| Mountable Kerb and Gutter | 58.211 | \$6,170.38 |
| Pattern Concrete Footpath | 1.503 | \$514.24 |
| Paving Footpath | 0.160 | \$66.65 |
| Property Access Rural | 377.465 | \$16,346.04 |
| Property Access Urban | 24.587 | \$1,083.92 |
| Quarry Dust Footpath | 13.037 | \$274.86 |

¹ IPWEA, 2011, Sec 4.2.6, Example of an Asset Management Plan Structure, pp 4|24 – 27.

| Asset category | Dimension (km) | Replacement Value (\$000) |
|------------------------------|----------------|---------------------------|
| Regional Road | 107.632 | \$26,661.35 |
| Resident Rural Gravel | 300.208 | \$19,561.93 |
| Resident Rural Sealed | 209.646 | \$26,218.71 |
| Resident Urban Gravel | 5.303 | \$332.37 |
| Resident Urban Sealed | 100.598 | \$20,909.81 |
| Formed | 6.412 | \$338.00 |
| Vehicular Track | 21.148 | \$727.12 |
| Road Bridge | 0.497 | \$7,032.32 |
| Spoon Drain | 0.083 | \$7.29 |
| Swing Bridge | 0.035 | \$47.25 |
| TOTAL | | \$173,365.90 |

Figure 5.1.1: Asset Age Profile



All figure values are shown in current day dollars.

Add discussion about the age asset profile. Outline how past peaks of investment that may require peaks in renewals in the future. Comment on the overall age versus useful lives of the assets.

5.1.2 Asset capacity and performance

Assets are generally provided to meet design standards where these are available. However, there is insufficient resources to address all known deficiencies. Locations where deficiencies in service performance are known are detailed in Table 5.1.2.

Table 5.1.2: Known Service Performance Deficiencies

| Location | Service Deficiency |
|--------------------------|---|
| Berrigan township | Some area lacking kerb and gutter and associated drainage |
| Finley Township | Some area with very flat kerb and no associated drainage |
| Rural road network | Many segments of road do not meet the adopted warrants in relation to width and clear zones |
| Lower River Road | Causeways are of substandard width and vertical alignment. Bridges and pavement are of substandard width. |
| Rural road intersections | No provision for turning traffic on most intersections |

| | |
|-------------------|-------------------------------------|
| Barooga Township | Footpaths as shown in updated PAMPS |
| Berrigan Township | Footpaths as shown in updated PAMPS |
| Finley Township | Footpaths as shown in updated PAMPS |
| Tocumwal township | Footpaths as shown in updated PAMPS |

The above service deficiencies were identified from Shire Officers experience and knowledge.

5.1.3 Asset condition

Condition is currently monitored in different ways for different assets as follows:

Sealed roads are regularly inspected and annually rated for condition;

Unsealed roads are regularly inspected but not formally rated for condition;

Kerb and Gutter is regularly inspected and a condition rating applied to obvious poor sections;

Footpaths are regularly inspected and formally rated for condition.

Bridges and Structures are regularly inspected and formally rated for condition.

Condition is measured using a 1 – 5 grading system⁴ as detailed in Table 5.1.3. It is important that consistent condition grades be used in reporting various assets across an organisation. This supports effective communication. At the detailed level assets may be measured utilising different condition scales, however, for reporting in the AM plan they are all translated to the 1 – 5 grading scale.


Table 5.1.3: Simple Condition Grading Model

| Condition Grading | Description of Condition |
|-------------------|---|
| 1 | Very Good: only planned maintenance required |
| 2 | Good: minor maintenance required plus planned maintenance |
| 3 | Fair: significant maintenance required |
| 4 | Poor: significant renewal/rehabilitation required |
| 5 | Very Poor: physically unsound and/or beyond rehabilitation |

The condition profile of our assets is shown in Figure 5.1.3.

Figure 5.1.3: Asset Condition Profile

⁴ IPWEA, 2015, IIMM, Sec 2.5.4, p 2|80.



As can be seen from the graph above, the majority of transport assets are in good to excellent condition. All assets are in a serviceable condition and those that are rated in Condition 4 are programmed for renewal.

All figure values are shown in current day dollars.

5.2 Operations and Maintenance Plan

Operations include regular activities to provide services. Examples of typical operational activities include cleaning, street sweeping, asset inspection, and utility costs.

Maintenance includes all actions necessary for retaining an asset as near as practicable to an appropriate service condition including regular ongoing day-to-day work necessary to keep assets operating. Examples of typical maintenance activities include pipe repairs, asphalt patching, and equipment repairs.

The trend in maintenance budgets are shown in Table 5.2.1.

Table 5.2.1: Maintenance Budget Trends

| Year | Maintenance Budget \$ |
|---------|-----------------------|
| | \$ |
| 2019/20 | \$3,146,500 |
| 2020/21 | \$2,619,500 |

Maintenance budget levels are considered to be adequate to meet projected service levels, which may be less than or equal to current service levels. Where maintenance budget allocations are such that they will result in a lesser level of service, the service consequences and service risks have been identified and are highlighted in this AM Plan and service risks considered in the Infrastructure Risk Management Plan.

Reactive maintenance is carried out in accordance with response levels of service detailed in Appendix C.

Asset hierarchy

An asset hierarchy provides a framework for structuring data in an information system to assist in collection of data, reporting information and making decisions. The hierarchy includes the asset class and component used for asset planning and financial reporting and service level hierarchy used for service planning and delivery.

The service hierarchy is shown in Table 5.2.2.

Table 5.2.2: Asset Service Hierarchy


| Service Hierarchy | Service Level Objective |
|--------------------|-------------------------|
| Regional Road Seal | Minimum width of 8.0m |

| | |
|---|--|
| Arterial Road Seal | Minimum width of 8.0m |
| Sealed Collector Road Seal | Minimum width of 7.5m |
| Gravel Collector Road Pavement | Minimum width of 6.2m |
| Sealed Residential Access Road Seal | Minimum width of 6.5m |
| Gravel Residential Access Road Pavement | Minimum width of 6.2m |
| Gravel Property Access Road Pavement | Minimum width of 5.0m |
| Formed Property Access Road Formation | Minimum width of 5.0m |
| Road Clear Zones | As per Berrigan Shire Council Roadside Hazard Treatment Policy |
| Kerb and Gutter | Minimum Fall of 1:300 |
| Footpath | Minimum width of 1.2m |
| Bridges and Structures | HML capacity and width to match road classification objectives |

Summary of forecast operations and maintenance costs

Forecast operations and maintenance costs are expected to vary in relation to the total value of the asset stock. If additional assets are acquired, the future operations and maintenance costs are forecast to increase. If assets are disposed of the forecast operation and maintenance costs are expected to decrease. Figure 5.2 shows the forecast operations and maintenance costs relative to the proposed operations and maintenance Planned Budget.

Figure 5.2: Operations and Maintenance Summary



All figure values are shown in current day dollars.

Maintenance and operational costs are expected to increase slightly for the forecast period to service acquisitions and budgets have been prepared to balance expected costs.

5.3 Renewal Plan

Renewal is major capital work which does not significantly alter the original service provided by the asset, but restores, rehabilitates, replaces or renews an existing asset to its original service potential. Work over and above restoring an asset to original service potential is considered to be an acquisition resulting in additional future operations and maintenance costs.

Assets requiring renewal are identified from one of two approaches in the Lifecycle Model.

- The first method uses Asset Register data to project the renewal costs (current replacement cost) and renewal timing (acquisition year plus updated useful life to determine the renewal year), or
- The second method uses an alternative approach to estimate the timing and cost of forecast renewal work (i.e. condition modelling system, staff judgement, average network renewals, or other).

The typical useful lives of assets used to develop projected asset renewal forecasts are shown in Table 5.3. Asset useful lives were last reviewed on 30 June, 2016 when transport assets were last revalued.⁵

Table 5.3: Useful Lives of Assets

| Asset (Sub)Category | Useful life |
|---|-------------|
| Arterial Road Formation | 1000 |
| Arterial Road Pavement | 50 |
| Arterial Road Seal | 15 |
| Asphalt Footpath | 25 |
| Asphalted Concrete Footpath | 80 |
| Barrier Kerb and Gutter | 80 |
| Brick Kerb and Gutter | 50 |
| Carpark Formation | 1000 |
| Carpark Pavement | 50 |
| Carpark Seal | 18 |
| Collector Gravel Road Formation | 1000 |
| Collector Gravel Road Pavement | 50 |
| Collector Sealed Road Formation | 1000 |
| Collector Sealed Road Pavement | 50 |
| Collector Sealed Road Seal | 15 |
| Concrete Footpath | 80 |
| Firetrail Formation | 1000 |
| Gravel Footpath | 30 |
| Kerb Only | 80 |
| Mountable Kerb and Gutter | 80 |
| Pattern Concrete Footpath | 80 |
| Paving Footpath | 50 |
| Property Access Rural Formed Road Formation | 1000 |

⁵ Enter Reference to Report documenting Review of Useful Life of Assets

| | |
|--|------|
| Property Access Rural Gravel Road Formation | 1000 |
| Property Access Rural Gravel Road Pavement | 50 |
| Property Access Urban Formed Road Formation | 1000 |
| Property Access Urban Gravel Road Formation | 1000 |
| Property Access Urban Gravel Road Pavement | 50 |
| Quarry Dust Footpath | 50 |
| Regional Road Formation | 1000 |
| Regional Road Pavement | 50 |
| Regional Road Seal | 12 |
| Residential Access Rural Gravel Road Formation | 1000 |
| Residential Access Rural Gravel Road Pavement | 50 |
| Residential Access Rural Sealed Road Formation | 1000 |
| Residential Access Rural Sealed Road Pavement | 50 |
| Residential Access Rural Sealed Road Seal | 15 |
| Residential Access Urban Gravel Road Formation | 1000 |
| Residential Access Urban Gravel Road Pavement | 50 |
| Residential Access Urban Sealed Road Formation | 1000 |
| Residential Access Urban Sealed Road Pavement | 50 |
| Residential Access Urban Sealed Road Seal | 18 |
| Road Bridge | 80 |
| Spoon Drain | 80 |
| Swing Bridge | 50 |

The estimates for renewals in this Asset Management Plan were based on the asset register.

5.3.1 Renewal ranking criteria

Asset renewal is typically undertaken to either:

- Ensure the reliability of the existing infrastructure to deliver the service it was constructed to facilitate (e.g. replacing a bridge that has a 5 t load limit), or

- To ensure the infrastructure is of sufficient quality to meet the service requirements (e.g. condition of a playground).⁶

It is possible to prioritise renewals by identifying assets or asset groups that:

- Have a high consequence of failure,
- Have high use and subsequent impact on users would be significant,
- Have higher than expected operational or maintenance costs, and
- Have potential to reduce life cycle costs by replacement with a modern equivalent asset that would provide the equivalent service.⁷

The ranking criteria used to determine priority of identified renewal proposals is detailed in Table 5.3.1.


Table 5.3.1: Renewal Priority Ranking Criteria

| Criteria | Weighting |
|------------------|-------------|
| Risk / Safety | 30% |
| Condition Rating | 25% |
| Road Hierarchy | 25% |
| Other Technical | 20% |
| Total | 100% |

5.4 Summary of future renewal costs

Forecast renewal costs are projected to increase over time if the asset stock increases. The forecast costs associated with renewals are shown relative to the proposed renewal budget in Figure 5.4.1. A detailed summary of the forecast renewal costs is shown in Appendix D.

Figure 5.4.1: Forecast Renewal Costs



All figure values are shown in current day dollars.

The average spend that is budgeted generally allows for renewal of assets as required. There is a significant backlog that should be addressed over the coming five years and then progress with renewal will need to be monitored as the mid term of the budget is approached at 2030 when some significant renewals are forecast.

⁶ IPWEA, 2015, IIMM, Sec 3.4.4, p 3|91.

⁷ Based on IPWEA, 2015, IIMM, Sec 3.4.5, p 3|97.

It is possible that these issues can be addressed by deferring renewals if condition ratings are favourable or alternatively the budget may have to be increased for this period.

5.5 Acquisition Plan

Acquisition reflects are new assets that did not previously exist or works which will upgrade or improve an existing asset beyond its existing capacity. They may result from growth, demand, social or environmental needs. Assets may also be donated to the Berrigan Shire Council.

5.5.1 Selection criteria

Proposed upgrade of existing assets, and new assets, are identified from various sources such as community requests, proposals identified by strategic plans or partnerships with others. Potential upgrade and new works should be reviewed to verify that they are essential to the Entities needs. Proposed upgrade and new work analysis should also include the development of a preliminary renewal estimate to ensure that the services are sustainable over the longer term. Verified proposals can then be ranked by priority and available funds and scheduled in future works programmes. The priority ranking criteria is detailed in Table 5.4.1.


Table 5.5.1: Acquired Assets Priority Ranking Criteria

| Criteria | Weighting |
|------------------|-------------|
| Risk / Safety | 30% |
| Condition Rating | 25% |
| Road Hierarchy | 25% |
| Other Technical | 20% |
| Total | 100% |

Summary of future asset acquisition costs

Forecast acquisition asset costs are summarised / summarised in Figure 5.4.1 and shown relative to the proposed acquisition budget. The forecast acquisition capital works program is shown in Appendix A.


Figure 5.5.1: Acquisition (Constructed) Summary



All figure values are shown in current day dollars.

When an Entity commits to new assets, they must be prepared to fund future operations, maintenance and renewal costs. They must also account for future depreciation when reviewing long term sustainability. When reviewing the long-term impacts of asset acquisition, it is useful to consider the cumulative value of the acquired assets being taken on by the Entity. The cumulative value of all acquisition work, including assets that are constructed and contributed shown in Figure 5.4.2.

Figure 5.5.2: Acquisition Summary



All figure values are shown in current dollars.

Expenditure on new assets and services in the capital works program will be accommodated in the long-term financial plan, but only to the extent that there is available funding.


Acquisitions will generally be associated with widening of rural roads to adopted service standards or the extension of the kerb and gutter and footpath networks to service the existing residential areas. There will be some donated assets received from property developments, however, there has been no attempt to factor these in as the development rate is unpredictable and they will have only a minor effect on the total asset quantum.

Summary of asset forecast costs

The financial projections from this asset plan are shown in Figure 5.4.3. These projections include forecast costs for acquisition, operation, maintenance, renewal, and disposal. These forecast costs are shown relative to the proposed budget.

The bars in the graphs represent the forecast costs needed to minimise the life cycle costs associated with the service provision. The proposed budget line indicates the estimate of available funding. The gap between the forecast work and the proposed budget is the basis of the discussion on achieving balance between costs, levels of service and risk to achieve the best value outcome.

Figure 5.5.3: Lifecycle Summary



All figure values are shown in current day dollars.

The proposed budget is adequate to service the predicted costs for the planning period, however, as previously mentioned, there is a significant backlog to be addressed over the coming five years and then progress with renewal will need to be monitored as the mid term of the budget is approached at 2030 when some significant renewals are forecast.

5.6 Disposal Plan

Disposal includes any activity associated with the disposal of a decommissioned asset including sale, demolition or relocation. Assets identified for possible decommissioning and disposal are shown in Table 5.6. A summary of the disposal costs and estimated reductions in annual operations and maintenance of disposing of the assets are also outlined in Table 5.6. Any costs or revenue gained from asset disposals is included in the long-term financial plan.

The only assets identified for disposal during life of this plan are components of the transport infrastructure that replaced prior to reaching their adopted useful life. These assets will have no revenue value and the remaining valuation will be written off the asset register as a book entry.

6.0 RISK MANAGEMENT PLANNING

The purpose of infrastructure risk management is to document the findings and recommendations resulting from the periodic identification, assessment and treatment of risks associated with providing services from infrastructure, using the fundamentals of International Standard ISO 31000:2018 Risk management – Principles and guidelines.

Risk Management is defined in ISO 31000:2018 as: ‘coordinated activities to direct and control with regard to risk’⁸.

An assessment of risks⁹ associated with service delivery will identify risks that will result in loss or reduction in service, personal injury, environmental impacts, a ‘financial shock’, reputational impacts, or other consequences. The risk assessment process identifies credible risks, the likelihood of the risk event occurring, and the consequences should the event occur. The risk assessment should also include the development of a risk rating, evaluation of the risks and development of a risk treatment plan for those risks that are deemed to be non-acceptable.

6.1 Critical Assets

Critical assets are defined as those which have a high consequence of failure causing significant loss or reduction of service. Critical assets have been identified and along with their typical failure mode, and the impact on service delivery, are summarised in Table 6.1. Failure modes may include physical failure, collapse or essential service interruption.

Table 6.1 Critical Assets

| Critical Asset(s) | Failure Mode | Impact |
|-------------------|---|--|
| Bridge Structures | Collapse/Damage due to overloading of flood event | Access along key roads prevented until repairs/alternative crossing can be completed |

By identifying critical assets and failure modes an organisation can ensure that investigative activities, condition inspection programs, maintenance and capital expenditure plans are targeted at critical assets.

6.2 Risk Assessment

The risk management process used is shown in Figure 6.2 below.

It is an analysis and problem-solving technique designed to provide a logical process for the selection of treatment plans and management actions to protect the community against unacceptable risks.

The process is based on the fundamentals of International Standard ISO 31000:2018.

⁸ ISO 31000:2009, p 2

⁹ REPLACE with Reference to the Corporate or Infrastructure Risk Management Plan as the footnote




Fig 6.2 Risk Management Process – Abridged
Source: ISO 31000:2018, Figure 1, p9

The risk assessment process identifies credible risks, the likelihood of the risk event occurring, the consequences should the event occur, development of a risk rating, evaluation of the risk and development of a risk treatment plan for non-acceptable risks.

An assessment of risks¹⁰ associated with service delivery will identify risks that will result in loss or reduction in service, personal injury, environmental impacts, a ‘financial shock’, reputational impacts, or other consequences.

Critical risks are those assessed with ‘Very High’ (requiring immediate corrective action) and ‘High’ (requiring corrective action) risk ratings identified in the Infrastructure Risk Management Plan. The residual risk and treatment costs of implementing the selected treatment plan is shown in Table 6.2. It is essential that these critical risks and costs are reported to management and the Berrigan Shire Council

Table 6.2: Risks and Treatment Plans

| Service or Asset at Risk | What can Happen | Risk Rating (VH, H) | Risk Treatment Plan | Residual Risk * | |
|---|--|----------------------------|--|------------------------|-------------------------------|
| | | | | | Treatment Costs \$,000 |
| Road Structure /Roadside furniture/ signs/ traffic | Damage to roads and signs etc and blockage of traffic lanes from traffic accident | Very High | Existing Procedures considered adequate | Very High | \$0 |

¹⁰ REPLACE with Reference to the Corporate or Infrastructure Risk Management Plan as the footnote

| | | | | | |
|--|--|------------------|---|------------------|----------------|
| Lower River Road/Taylors Road/Bushlands Road | Road can be impassable and damaged due to flooding | High | Ensure staff are aware of monitoring requirements and procedures and have suitable resources for road closures | High | \$5 |
| All roads and streets | Trees and debris blocking traffic lanes and damaging road furniture | Very High | Existing Procedures considered adequate | Very High | \$0 |
| Rural Road | Vehicle collision with wildlife | Very High | Existing Procedures considered adequate | Very High | \$0 |
| Rural Road | Vehicle collision with livestock | Very High | Existing Procedures considered adequate | Very High | \$0 |
| Rural Road | Vehicle collision with livestock associated with travelling stock | Very High | Existing Procedures considered adequate | Very High | \$0 |
| Rural Road | Vehicle collision with livestock at stock crossing | Very High | Improved signage and maintenance and encourage owners to Construct Underpasses | High | \$5 |
| Lower River Road concrete causeways | Vehicle accident due to narrow crossing and poor vertical alignment | Very High | Upgrade causeways | High | \$800 |
| Lower River Road Bridges | Vehicle accident due to narrow bridges and approaches | Very High | upgrade bridges with a preference to replacing bridges with causeways | High | \$2,550 |
| Lower River Road , Taylors Road, Tocomwal Boat Ramp Access, Town Beach Road, MR 226 Barooga | Damaged by floodwaters | High | Routine maintenance and improvement. Monitor condition of roads and structures to allow for emergency relief funding to be obtained. | High | \$52 |
| Rural Road | Traffic accident due to narrow pavement | Very High | Develop program to upgrade council roads to adopted widths | very high | \$1,000 |
| Rural Road | Traffic accident due to inadequate clearance to roadside obstacles | Very High | Develop program to clear roadsides of obstacles | very high | \$500 |

| | | | | | |
|--|---|------------------|---|------------------|--------------|
| Rural road intersection | Traffic accident due to no right turn lanes | Very High | Provide right turn lanes where traffic warrants and intersections are being reconstructed | very high | \$100 |
| Footpath | Trip / Fall | High | Update SOP's for Footpath inspection and maintenance | High | \$0 |
| Pedestrian Crossing | Pedestrian colliding with vehicle | Very High | Existing Procedures considered adequate | Very High | \$0 |
| Road Bridge | Collapse due to Age, structural fatigue, Not built for current/future loadings | High | Devlop SOP"s for Bridge Inspection and maintenance | High | \$5 |
| Rural Roads | Vehicle accident due to faded or missing linemarking | High | Adequate provision made in works budget for remarking faded linemarking and marking new works. Develop a procurement agreement that requires linemarking contractor to complete works within 7 days of order. | High | \$10 |
| Railway Level Crossings Tuppal Road and Browne Street | Vehicle/Pedestrian collision with Train | High | Existing Procedures considered adequate | High | \$0 |
| Rural Roads | Collision involving school bus/children | High | Develop procedures for ongoing updating of changes to school bus routes. Determine and adopt standards for school bus routes and bus stops and adopt a programme for the ongoing improvement of school bus routes. | Medium | \$0 |
| Road pavements | Pavement failure due to inadequate strength | High | Progressively upgrade road pavements on a priority basis based on condition and risk ratings. | High | \$510 |
| Paved Footpaths | Visually impaired pedestrians could | High | Upgrade tactile markings on all Priority Level 1 | High | \$20 |

| | | | | | |
|---|---|-------------|--|---------------|----------------|
| | <i>walk into traffic or fall</i> | | <i>paths to AS1428.4 compliance</i> | | |
| Urban Roads | Vehicles could collide with pedestrians walking along urban roads. | High | Construct paved footpaths on urban roads and streets in accordance with priorities determined in the Pedestrian Access and Mobility Plan for each town | High | \$150 |
| Intersection of Golf Course Road and Vermont Street, Barooga | Vehicle collision with pedestrian | High | Reconfigure intersection to provide more direct and safer pedestrian linkages on all 4 approaches | High | \$150 |
| Chanter Street (Riverina Highway), Berrigan | Vehicle collision with pedestrian | High | Construct a pedestrian crossing point in front of the Berrigan Library with build out protection to the edge of the traffic lanes. | High | \$10 |
| intersection of Chanter Street and Jerilderie Street, Berrigan | Vehicle collision with pedestrian | High | Construct a pedestrian crossing point from the south east corner of Jerilderie Street/Chanter Street to the north west corner of Jerilderie Street/Carter Street. | High | \$10 |
| Pedestrian Crossing, Murray Street, Finley | Vehicle collision with pedestrian | High | Relocate the Pedestrian Crossing north of the intersection. | High | #VALUE! |
| Footpaths and Walking/Cycling Tracks | Pedestrians or cyclists could fall down slopes on verges of paths | High | Provide guidepost delineation and/or barriers on paths/cycle tracks with steep batters or drop offs. | High | \$17 |
| Concrete Footpaths | Pedestrians could trip or fall as a result of excessive drop off at edge of concrete paths | High | Place fill along edge of concrete paths where there is a drop off | Medium | \$10 |

| | | | | | |
|--|--|-------------|---|---------------|--------------|
| Endeavour Street carparks, Finley | <i>Pedestrians could trip and fall and disabled could be hit by vehicles on road due to no pedestrian connections</i> | High | <i>Construct concrete path connections from carparks in Endeavour Street to public toilets and Railway Park entrance path.</i> | Medium | \$9 |
| Bushlands Road-Jerilderie Street intersection, Tocumwal | <i>Pedestrian connections from Levee walk through Pony Club and across Jerilderie Street are not provided</i> | High | <i>Provide gravel path connection from the levee path in the Tocumwal Pony Club to the path on the north side of Jerilderie Street at Bushlands Road</i> | High | \$20 |
| Sealed Rural Roads - Cross Intersections | <i>Vehicle collision</i> | High | <i>Progressively reconfigure sealed rural roads cross intersections to staggered T intersections on a priority basis</i> | High | \$200 |
| Unsealed Rural Roads | <i>Vehicle collision due to Vehicles traversing Road construction works or maintenance works in progress.</i> | High | <i>Existing Procedures considered adequate</i> | High | 0 |
| Sealed Rural Roads | <i>Vehicle collision due to Vehicles traversing Road construction works or maintenance works in progress.</i> | High | <i>Existing Procedures considered adequate</i> | High | 0 |
| Footpaths and Walking/Cycling Tracks | <i>Pedestrians or cyclists fall while traversing path/track construction works or maintenance works in progress.</i> | High | <i>Existing Procedures considered adequate</i> | High | 0 |

Note * The residual risk is the risk remaining after the selected risk treatment plan is implemented.

6.3 Infrastructure Resilience Approach

The resilience of our critical infrastructure is vital to the ongoing provision of services to customers. To adapt to changing conditions we need to understand our capacity to 'withstand a given level of stress or demand', 1 and to respond to possible disruptions to ensure continuity of service.

Resilience is built on aspects such as response and recovery planning, financial capacity, climate change and crisis leadership.

We do not currently measure our resilience in service delivery. This will be included in future iterations of the Asset Management Plan.

6.4 Service and Risk Trade-Offs

The decisions made in adopting this AM Plan are based on the objective to achieve the optimum benefits from the available resources.

6.4.1 What we cannot do

There are some operations and maintenance activities and capital projects that are unable to be undertaken within the next 10 years. These include:

- Widening of all bridge structures to the adopted service levels.
- Widening of all roads to the adopted service levels.
- Extension of footpath network to extend identified in the Pedestrian Access and Mobility Plans.
- Extension of kerb and gutter network to service all residential streets.

6.4.2 Service trade-off

If there is forecast work (operations, maintenance, renewal, acquisition or disposal) that cannot be undertaken due to available resources, then this will result in service consequences for users. These service consequences include:

- Road Safety is compromised.
- Pedestrian Safety is compromised.
- Street amenity is reduced where open earth drains remain.

6.4.3 Risk trade-off

The operations and maintenance activities and capital projects that cannot be undertaken may sustain or create risk consequences. These risk consequences include:

- Greater risk of personal and property damage and possible compensation claims against Council.
- Increased maintenance costs where road width is not fit for traffic conditions.

These actions and expenditures are considered and included in the forecast costs, and where developed, the Risk Management Plan.

7.0 FINANCIAL SUMMARY


This section contains the financial requirements resulting from the information presented in the previous sections of this Asset Management Plan. The financial projections will be improved as the discussion on desired levels of service and asset performance matures.

7.1 Financial Statements and Projections

7.1.1 Asset valuations

The best available estimate of the value of assets included in this Asset Management Plan are shown below. The assets are valued at fair value:

| | |
|--|----------------------|
| Current (Gross) Replacement Cost | \$173,365,905 |
| Depreciable Amount | \$173,365,905 |
| Depreciated Replacement Cost ¹¹ | \$123,905,834 |
| Depreciation | \$2,785,348 |



7.1.2 Sustainability of service delivery

There are two key indicators of sustainable service delivery that are considered in the Asset Management Plan for this service area. The two indicators are the:

- asset renewal funding ratio (proposed renewal budget for the next 10 years / forecast renewal costs for next 10 years), and
- medium term forecast costs/proposed budget (over 10 years of the planning period).

Asset Renewal Funding Ratio

Asset Renewal Funding Ratio¹² 107%

The Asset Renewal Funding Ratio is an important indicator and illustrates that over the next 10 years we expect to have 107% of the funds required for the optimal renewal of assets.

The forecast renewal work along with the proposed renewal budget, and the cumulative shortfall, is illustrated in Appendix D.

Medium term – 10 year financial planning period

This Asset Management Plan identifies the forecast operations, maintenance and renewal costs required to provide an agreed level of service to the community over a 10 year period. This provides input into 10 year financial and funding plans aimed at providing the required services in a sustainable manner.

This forecast work can be compared to the proposed budget over the 10 year period to identify any funding shortfall.

The forecast operations, maintenance and renewal costs over the 10 year planning period is \$4,654,112 on average per year.

The proposed (budget) operations, maintenance and renewal funding is \$5,896,345 on average per year giving a 10 year funding excess of \$124,223 per year. This indicates that 102% of the forecast costs needed to provide the services documented in this Asset Management Plan are accommodated in the proposed budget. This excludes acquired assets.

¹¹ Also reported as Written Down Value, Carrying or Net Book Value.

¹² AIFMM, 2015, Version 1.0, Financial Sustainability Indicator 3, Sec 2.6, p 9.

Providing sustainable services from infrastructure requires the management of service levels, risks, forecast outlays and financing to achieve a financial indicator of approximately 1.0 for the first years of the Asset Management Plan and ideally over the 10 year life of the Long-Term Financial Plan.

7.1.3 Forecast Costs (outlays) for the long-term financial plan

Table 7.1.3 shows the forecast costs (outlays) for the 10 year long-term financial plan.

Forecast costs are shown in 2020 dollar values.

Table 7.1.3: Forecast Costs (Outlays) for the Long-Term Financial Plan

| Year | Forecast Acquisition | Forecast Operation | Forecast Maintenance | Forecast Renewal | Forecast Disposal |
|---------|----------------------|--------------------|----------------------|------------------|-------------------|
| 2020 | \$741,500 | \$1,223,000 | \$3,146,007 | \$2,159,700 | \$0 |
| 2021 | \$514,200 | \$1,244,000 | \$2,619,520 | \$1,807,300 | \$0 |
| 2022 | \$718,400 | \$1,249,118 | \$2,630,297 | \$1,784,500 | \$0 |
| 2023 | \$652,000 | \$1,253,763 | \$2,640,078 | \$1,890,000 | \$0 |
| 2024 | \$478,200 | \$1,257,169 | \$2,647,251 | \$2,251,000 | \$0 |
| 2025 | \$496,000 | \$1,260,703 | \$2,654,692 | \$1,742,000 | \$0 |
| 2026 | \$460,000 | \$1,263,980 | \$2,661,592 | \$1,950,000 | \$0 |
| 2027 | \$460,000 | \$1,267,257 | \$2,668,493 | \$1,930,000 | \$0 |
| 2028 | \$460,000 | \$1,270,534 | \$2,675,393 | \$1,930,000 | \$0 |
| 2029 | \$460,000 | \$1,273,811 | \$2,682,294 | \$1,930,000 | \$0 |
| 2030 | \$460,000 | \$1,277,088 | \$2,689,194 | \$1,930,000 | \$0 |
| 2031 | \$460,000 | \$1,280,365 | \$2,696,095 | \$1,980,000 | \$0 |
| 1980000 | \$410000 | \$1,283,286 | \$2,702,245 | \$1,980,000 | \$0 |
| 1980000 | \$410000 | \$1,286,207 | \$2,708,396 | \$1,980,000 | \$0 |
| 1980000 | \$410000 | \$1,289,128 | \$2,714,546 | \$1,980,000 | \$0 |
| 1980000 | \$410000 | \$1,292,048 | \$2,720,697 | \$1,980,000 | \$0 |
| 1980000 | \$410000 | \$1,294,969 | \$2,726,847 | \$1,980,000 | \$0 |
| 1980000 | \$410000 | \$1,297,890 | \$2,732,998 | \$1,980,000 | \$0 |
| 1980000 | \$410000 | \$1,300,811 | \$2,739,148 | \$1,980,000 | \$0 |
| 1980000 | \$410000 | \$1,303,732 | \$2,745,298 | \$1,980,000 | \$0 |

7.2 Funding Strategy

The proposed funding for assets is outlined in the Entity's budget and Long-Term financial plan.

The financial strategy of the entity determines how funding will be provided, whereas the Asset Management Plan communicates how and when this will be spent, along with the service and risk consequences of various service alternatives.

7.3 Valuation Forecasts

Asset values are forecast to increase as additional assets are added.

Additional assets will generally add to the operations and maintenance needs in the longer term. Additional assets will also require additional costs due to future renewals. Any additional assets will also add to future depreciation forecasts.

7.4 Key Assumptions Made in Financial Forecasts

In compiling this Asset Management Plan, it was necessary to make some assumptions. This section details the key assumptions made in the development of this AM plan and should provide readers with an understanding of the level of confidence in the data behind the financial forecasts.

Key assumptions made in this Asset Management Plan are:

| Key Assumptions | Risks of Change to Assumptions |
|---|--|
| The useful lives of rural road assets have been reviewed on the basis of condition and roughness reports and these will be required to be updated prior to the next review of the plan. | Changes to traffic conditions or extreme wet conditions could accelerate deterioration |
| For sealed roads carrying less than 80 vehicles per day a lifecycle of 100 years has been assumed regardless of condition and roughness measures. Should dangerous conditions materialise on these roads they will be corrected by maintenance strategies including heavy patching. | Changes to traffic conditions could accelerate deterioration |
| The urban street network and bridges have not had condition ratings carried out and these need to be done to improve the accuracy of this plan. | Condition inspections may generate additional works for repairs |
| Bitumen reseals have been considered as capital renewal works for this plan | Nil |
| The useful life of footpath assets has been taken from the asset management model | Review of useful life's on the basis of condition could change required annual expenditure |
| It is assumed that asset utilisation frequency will not change | Acceleration / deceleration of asset condition |

7.5 Forecast Reliability and Confidence

The forecast costs, proposed budgets, and valuation projections in this AM Plan are based on the best available data. For effective asset and financial management, it is critical that the information is current and accurate. Data confidence is classified on a A - E level scale¹³ in accordance with Table 7.5.1.

Table 7.5.1: Data Confidence Grading System

| Confidence Grade | Description |
|--------------------|--|
| A. Highly reliable | Data based on sound records, procedures, investigations and analysis, documented properly and agreed as the best method of assessment. Dataset is complete and estimated to be accurate $\pm 2\%$ |
| B. Reliable | Data based on sound records, procedures, investigations and analysis, documented properly but has minor shortcomings, for example some of the data is old, some documentation is missing and/or reliance is placed on unconfirmed reports or some extrapolation. Dataset is complete and estimated to be accurate $\pm 10\%$ |
| C. Uncertain | Data based on sound records, procedures, investigations and analysis which is incomplete or unsupported, or extrapolated from a limited sample for which grade A or B data are available. Dataset is substantially complete but up to 50% is extrapolated data and accuracy estimated $\pm 25\%$ |
| D. Very Uncertain | Data is based on unconfirmed verbal reports and/or cursory inspections and analysis. Dataset may not be fully complete, and most data is estimated or extrapolated. Accuracy $\pm 40\%$ |
| E. Unknown | None or very little data held. |

¹³ IPWEA, 2015, IIMM, Table 2.4.6, p 2 | 71.

The estimated confidence level for and reliability of data used in this AM Plan is shown in Table 7.5.2.

Table 7.5.2: Data Confidence Assessment for Data used in AM Plan

| Data | Confidence Assessment | Comment |
|---|-----------------------|-------------------------------|
| Demand drivers | Medium | Based on current figures |
| Growth projections | Medium | Based on current figures |
| Operations expenditures | High | Based on current actual costs |
| Maintenance expenditures | High | Based on current actual costs |
| Projected Renewal exps. - Asset values | High | Based on current actual costs |
| - Asset residual values | High | Based on current actual costs |
| - Asset useful lives | High | Based on current actual costs |
| - Condition modelling | High | Based on current actual costs |
| - Network renewals | High | Based on current actual costs |
| - Defect repairs | High | Based on current actual costs |
| Upgrade/New expenditures | High | Based on current actual costs |
| Disposal expenditures | N/A | N/A |

Over all data sources, the data confidence is assessed as high confidence level for data used in the preparation of this AM Plan.

8.0 PLAN IMPROVEMENT AND MONITORING

8.1 Status of Asset Management Practices¹⁴

8.1.1 Accounting and financial data sources

This Asset Management Plan utilises accounting and financial data. The source of the data is Council's 'Practical' accounting software.

8.1.2 Asset management data sources

This Asset Management Plan also utilises asset management data. The source of the data is Council's 'AssetFinda' asset management system in conjunction with MapInfo mapping and database.

8.2 Improvement Plan

It is important that an entity recognise areas of their Asset Management Plan and planning process that require future improvements to ensure effective asset management and informed decision making. The improvement plan generated from this Asset Management Plan is shown in Table 8.2.

Table 8.2: Improvement Plan

| Task | Task | Responsibility | Resources Required | Timeline |
|------|--|----------------|--------------------|-----------|
| 1 | Condition rating of Assets | ESM | Staff | June 2023 |
| 2 | Review remaining life of assets | ESM | Staff | June 2023 |
| 3 | Componentisation of assets such as drainage structures, signs and traffic facilities including review of unit costs | ESM | Staff | June 2023 |
| 4 | Develop chart of accounts to allow separation of operation costs and maintenance costs and to split the maintenance costs into reactive, planned and cyclic and to separate capital expenditure into renewal, new and upgrade works. | FM | Staff | June 2023 |
| 5 | Investigate options to integrate Asset Management system with the Accounting / financial system | DTS DCS ESM FM | Staff | June 2023 |
| 6 | Review customer request /complaint settings in customer request management system to reflect desirable data being collected | AOM | Staff | June 2022 |
| 7 | Ensure all assets in Asset Management System have a condition score | AOM | Staff | June 2021 |
| 8 | | | | |
| 9 | | | | |
| 10 | | | | |

¹⁴ ISO 55000 Refers to this the Asset Management System

8.3 Monitoring and Review Procedures

This Asset Management Plan will be reviewed during the annual budget planning process and revised to show any material changes in service levels, risks, forecast costs and proposed budgets as a result of budget decisions.

The AM Plan will be reviewed and updated annually to ensure it represents the current service level, asset values, forecast operations, maintenance, renewals, upgrade/new and asset disposal costs and proposed budgets. These forecast costs and proposed budget are incorporated into the Long-Term Financial Plan or will be incorporated into the Long-Term Financial Plan once completed.

The AM Plan has a maximum life of 4 years and is due for complete revision and updating within 2 years of each Berrigan Shire Council election.

8.4 Performance Measures

The effectiveness of this Asset Management Plan can be measured in the following ways:

- The degree to which the required forecast costs identified in this Asset Management Plan are incorporated into the long-term financial plan,
- The degree to which the 1-5 year detailed works programs, budgets, business plans and corporate structures take into account the 'global' works program trends provided by the Asset Management Plan,
- The degree to which the existing and projected service levels and service consequences, risks and residual risks are incorporated into the Strategic Plan and associated plans,
- The Asset Renewal Funding Ratio achieving the Organisational target (this target is often 1.0).

9.0 REFERENCES

- IPWEA, 2006, 'International Infrastructure Management Manual', Institute of Public Works Engineering Australasia, Sydney, www.ipwea.org/IIMM
- IPWEA, 2008, 'NAMS.PLUS Asset Management', Institute of Public Works Engineering Australasia, Sydney, www.ipwea.org/namsplus.
- IPWEA, 2015, 2nd edn., 'Australian Infrastructure Financial Management Manual', Institute of Public Works Engineering Australasia, Sydney, www.ipwea.org/AIFMM.
- IPWEA, 2015, 3rd edn., 'International Infrastructure Management Manual', Institute of Public Works Engineering Australasia, Sydney, www.ipwea.org/IIMM
- IPWEA, 2012 LTFP Practice Note 6 PN Long-Term Financial Plan, Institute of Public Works Engineering Australasia, Sydney
- ISO, 2018, ISO 31000:2018, Risk management – Guidelines
- Berrigan Shire Council Asset Management Strategy 2020 – 2030,
- Berrigan Shire Council Asset Accounting Policy 2020
- Berrigan Shire Council Annual Report, Management Plan, Financial Statements and Budget.

10.0APPENDICES

Appendix A Acquisition Forecast

A.1 – Acquisition Forecast Assumptions and Source

Acquisitions will generally be associated with widening of rural roads to adopted service standards or the extension of the kerb and gutter and footpath networks to service the existing residential areas. There will be some donated assets received from property developments, however, there has been no attempt to factor these in as the development rate is unpredictable and they will have only a minor effect on the total asset quantum.

A.2 – Acquisition Project Summary

The project titles included in the lifecycle forecast are included here.

| Year | Project | \$ Estimate |
|------|---------------------------------|-------------|
| 2020 | Footpath Network Extension | 211000 |
| 2020 | Kerb & Gutter Network Extension | 135000 |
| 2020 | Road widening | 395500 |
| 2021 | Road widening | 292000 |
| 2021 | Kerb & Gutter Network Extension | 124000 |
| 2021 | Footpath Network Extension | 98200 |
| 2022 | Footpath Network Extension | 116400 |
| 2022 | Kerb & Gutter Network Extension | 293000 |
| 2022 | Road widening | 309000 |
| 2023 | Road widening | 310000 |
| 2023 | Kerb & Gutter Network Extension | 272000 |
| 2023 | Footpath Network Extension | 70000 |
| 2024 | Footpath Network Extension | 29200 |
| 2024 | Kerb & Gutter Network Extension | 100000 |
| 2024 | Road widening | 349000 |
| 2025 | Road widening | 320000 |
| 2025 | Kerb & Gutter Network Extension | 100000 |
| 2025 | Footpath Network Extension | 76000 |
| 2026 | Footpath Network Extension | 40000 |
| 2026 | Kerb & Gutter Network Extension | 100000 |
| 2026 | Road widening | 320000 |
| 2027 | Road widening | 320000 |
| 2027 | Kerb & Gutter Network Extension | 100000 |
| 2027 | Footpath Network Extension | 40000 |
| 2028 | Footpath Network Extension | 40000 |
| 2028 | Kerb & Gutter Network Extension | 100000 |
| 2028 | Road widening | 320000 |
| 2029 | Road widening | 320000 |
| 2029 | Kerb & Gutter Network Extension | 100000 |
| 2029 | Footpath Network Extension | 40000 |
| 2030 | Footpath Network Extension | 40000 |
| 2030 | Kerb & Gutter Network Extension | 100000 |
| 2030 | Road widening | 320000 |

| | | |
|------|---------------------------------|--------|
| 2031 | Road widening | 320000 |
| 2031 | Kerb & Gutter Network Extension | 100000 |
| 2031 | Footpath Network Extension | 40000 |
| 2032 | Footpath Network Extension | 40000 |
| 2032 | Kerb & Gutter Network Extension | 50000 |
| 2032 | Road widening | 320000 |
| 2033 | Road widening | 320000 |
| 2033 | Kerb & Gutter Network Extension | 50000 |
| 2033 | Footpath Network Extension | 40000 |
| 2034 | Footpath Network Extension | 40000 |
| 2034 | Kerb & Gutter Network Extension | 50000 |
| 2034 | Road widening | 320000 |
| 2035 | Road widening | 320000 |
| 2035 | Kerb & Gutter Network Extension | 50000 |
| 2035 | Footpath Network Extension | 40000 |
| 2036 | Footpath Network Extension | 40000 |
| 2036 | Kerb & Gutter Network Extension | 50000 |
| 2036 | Road widening | 320000 |
| 2037 | Road widening | 320000 |
| 2037 | Kerb & Gutter Network Extension | 50000 |
| 2037 | Footpath Network Extension | 40000 |
| 2038 | Footpath Network Extension | 40000 |
| 2038 | Kerb & Gutter Network Extension | 50000 |
| 2038 | Road widening | 320000 |
| 2039 | Road widening | 320000 |
| 2039 | Kerb & Gutter Network Extension | 50000 |
| 2039 | Footpath Network Extension | 40000 |

Insert Acquisition table with year project \$Estimate titles.

A.3 – Acquisition Forecast Summary

Table A3 - Acquisition Forecast Summary

| Year | Constructed | Contributed | Planned Budget |
|------|-------------|-------------|----------------|
| 2020 | 741500 | 0 | 0 |
| 2021 | 514200 | 0 | 0 |
| 2022 | 718400 | 0 | 0 |
| 2023 | 652000 | 0 | 0 |
| 2024 | 478200 | 0 | 0 |
| 2025 | 496000 | 0 | 0 |

| | | | |
|------|--------|---|---|
| 2026 | 460000 | 0 | 0 |
| 2027 | 460000 | 0 | 0 |
| 2028 | 460000 | 0 | 0 |
| 2029 | 460000 | 0 | 0 |
| 2030 | 460000 | 0 | 0 |
| 2031 | 460000 | 0 | 0 |
| 2032 | 410000 | 0 | 0 |
| 2033 | 410000 | 0 | 0 |
| 2034 | 410000 | 0 | 0 |
| 2035 | 410000 | 0 | 0 |
| 2036 | 410000 | 0 | 0 |
| 2037 | 410000 | 0 | 0 |
| 2038 | 410000 | 0 | 0 |
| 2039 | 410000 | 0 | 0 |

Appendix B Operation Forecast

B.1 – Operation Forecast Assumptions and Source

Operational costs are expected to increase slightly for the forecast period to service acquisitions and budgets have been prepared to balance expected costs.

B.2 – Operation Forecast Summary

Table B2 - Operation Forecast Summary

| Year | Operation Forecast | Additional Operation Forecast | Total Operation Forecast |
|------|--------------------|-------------------------------|--------------------------|
| 2020 | 1223000 | 0 | 1223000 |
| 2021 | 1244000 | 0 | 1244000 |
| 2022 | 1249117 | 0 | 1249117 |
| 2023 | 1253762 | 0 | 1253762 |
| 2024 | 1257169 | 0 | 1257169 |
| 2025 | 1260702 | 0 | 1260702 |
| 2026 | 1263979 | 0 | 1263979 |
| 2027 | 1267257 | 0 | 1267257 |
| 2028 | 1270534 | 0 | 1270534 |
| 2029 | 1273811 | 0 | 1273811 |
| 2030 | 1277088 | 0 | 1277088 |
| 2031 | 1280365 | 0 | 1280365 |
| 2032 | 1283285 | 0 | 1283285 |
| 2033 | 1286206 | 0 | 1286206 |
| 2034 | 1289127 | 0 | 1289127 |
| 2035 | 1292048 | 0 | 1292048 |
| 2036 | 1294969 | 0 | 1294969 |
| 2037 | 1297890 | 0 | 1297890 |
| 2038 | 1300810 | 0 | 1300810 |
| 2039 | 1303732 | 0 | 1303732 |

Appendix C Maintenance Forecast

C.1 – Maintenance Forecast Assumptions and Source

Maintenance costs are expected to increase slightly for the forecast period to service acquisitions and budgets have been prepared to balance expected costs.

C.2 – Maintenance Forecast Summary

Table C2 - Maintenance Forecast Summary

| Year | Forecast | Additional Costs | Additional Forecast | Total Forecast |
|------|------------|------------------|---------------------|----------------|
| 2020 | 3146007 | | 0 | 3146007 |
| 2021 | 2619520 | 0 | 0 | 2619520 |
| 2022 | 2630296.75 | 0 | 0 | 2630296.75 |
| 2023 | 2640077.5 | 0 | 0 | 2640077.5 |
| 2024 | 2647251 | 0 | 0 | 2647251 |
| 2025 | 2654691.75 | 0 | 0 | 2654691.75 |
| 2026 | 2661592.25 | 0 | 0 | 2661592.25 |
| 2027 | 2668492.75 | 0 | 0 | 2668492.75 |
| 2028 | 2675393.25 | 0 | 0 | 2675393.25 |
| 2029 | 2682293.75 | 0 | 0 | 2682293.75 |
| 2030 | 2689194.25 | 0 | 0 | 2689194.25 |
| 2031 | 2696094.75 | 0 | 0 | 2696094.75 |
| 2032 | 2702245.25 | 0 | 0 | 2702245.25 |
| 2033 | 2708395.75 | 0 | 0 | 2708395.75 |
| 2034 | 2714546.25 | 0 | 0 | 2714546.25 |
| 2035 | 2720696.5 | 0 | 0 | 2720696.5 |
| 2036 | 2726847 | 0 | 0 | 2726847 |
| 2037 | 2732997.5 | 0 | 0 | 2732997.5 |
| 2038 | 2739148 | 0 | 0 | 2739148 |
| 2039 | 2745298.5 | 0 | 0 | 2745298.5 |

Appendix D Renewal Forecast Summary

D.1 – Renewal Forecast Assumptions and Source

Asset renewals are determined using Asset Register data to project the renewal costs (current replacement cost) and renewal timing (acquisition year plus updated useful life to determine the renewal year). The useful life of assets is reviewed periodically following condition assessments of the assets and a reassessment of the remaining useful life. A spreadsheet has been developed for the assessment of road pavement assets and renewal priorities have been heavily weighted to roads that carry higher volumes of traffic.

The typical useful lives of assets used to develop projected asset renewal forecasts are shown in Table 5.3. Asset useful lives were last reviewed on 30 June, 2016 when transport assets were last revalued.¹⁵

Table 5.3: Useful Lives of Assets

| Asset (Sub)Category | Useful life |
|---------------------------------|-------------|
| Arterial Road Formation | 1000 |
| Arterial Road Pavement | 50 |
| Arterial Road Seal | 15 |
| Asphalt Footpath | 25 |
| Asphalted Concrete Footpath | 80 |
| Barrier Kerb and Gutter | 70-80 |
| Brick Kerb and Gutter | 50 |
| Carpark Formation | 1000 |
| Carpark Pavement | 50 |
| Carpark Seal | 18 |
| Collector Gravel Road Formation | 1000 |
| Collector Gravel Road Pavement | 50 |
| Collector Sealed Road Formation | 1000 |
| Collector Sealed Road Pavement | 50 |
| Collector Sealed Road Seal | 15 |
| Concrete Footpath | 70-80 |
| Firetrail Formation | 1000 |
| Gravel Footpath | 30 |
| Kerb Only | 80 |
| Mountable Kerb and Gutter | 80 |

¹⁵

| | |
|--|-------|
| Pattern Concrete Footpath | 80 |
| Paving Footpath | 50 |
| Property Access Rural Formed Road Formation | 1000 |
| Property Access Rural Gravel Road Formation | 1000 |
| Property Access Rural Gravel Road Pavement | 50 |
| Property Access Urban Formed Road Formation | 1000 |
| Property Access Urban Gravel Road Formation | 1000 |
| Property Access Urban Gravel Road Pavement | 50 |
| Quarry Dust Footpath | 50 |
| Regional Road Formation | 1000 |
| Regional Road Pavement | 30-50 |
| Regional Road Seal | 12 |
| Residential Access Rural Gravel Road Formation | 1000 |
| Residential Access Rural Gravel Road Pavement | 50 |
| Residential Access Rural Sealed Road Formation | 1000 |
| Residential Access Rural Sealed Road Pavement | 50 |
| Residential Access Rural Sealed Road Seal | 15 |
| Residential Access Urban Gravel Road Formation | 1000 |
| Residential Access Urban Gravel Road Pavement | 50 |
| Residential Access Urban Sealed Road Formation | 1000 |
| Residential Access Urban Sealed Road Pavement | 50 |
| Residential Access Urban Sealed Road Seal | 18 |
| Road Bridge | 80 |
| Spoon Drain | 80 |
| Swing Bridge | 50 |

The estimates for renewals in this Asset Management Plan were based on the asset register.

The average spend that is budgeted generally allows for renewal of assets as required. There is a significant backlog that should be addressed over the coming five years and then progress with renewal will need to be monitored as the mid term of the budget is approached at 2030 when some significant renewals are forecast. It is possible that these issues can be addressed by deferring renewals if condition ratings are favourable or alternatively the budget may have to be increased for this period.

D.2 – Renewal Project Summary

The project renewals included in the lifecycle forecast are summarized here.

| Year | Total | Kerb & Gutter | Footpaths | Roads |
|------|---------|---------------|-----------|---------|
| 2020 | 2159700 | 235000 | 10000 | 1914700 |
| 2021 | 1807300 | 120000 | 50000 | 1637300 |
| 2022 | 1784500 | 40000 | 20000 | 1724500 |
| 2023 | 1890000 | 40000 | 50000 | 1800000 |
| 2024 | 2251000 | 225000 | 80000 | 1946000 |
| 2025 | 1742000 | 100000 | 50000 | 1592000 |
| 2026 | 1950000 | 100000 | 50000 | 1800000 |
| 2027 | 1930000 | 100000 | 30000 | 1800000 |
| 2028 | 1930000 | 100000 | 30000 | 1800000 |
| 2029 | 1930000 | 100000 | 30000 | 1800000 |
| 2030 | 1930000 | 100000 | 30000 | 1800000 |
| 2031 | 1980000 | 150000 | 30000 | 1800000 |
| 2032 | 1980000 | 150000 | 30000 | 1800000 |
| 2033 | 1980000 | 150000 | 30000 | 1800000 |
| 2034 | 1980000 | 150000 | 30000 | 1800000 |
| 2035 | 1980000 | 150000 | 30000 | 1800000 |
| 2036 | 1980000 | 150000 | 30000 | 1800000 |
| 2037 | 1980000 | 150000 | 30000 | 1800000 |
| 2038 | 1980000 | 150000 | 30000 | 1800000 |
| 2039 | 1980000 | 150000 | 30000 | 1800000 |

D.3 – Renewal Forecast Summary

Table D3 - Renewal Forecast Summary

| Year | Renewal Forecast | Renewal Budget |
|------|------------------|----------------|
| 2020 | 6480245 | 2159700 |
| 2021 | 688992 | 1807300 |
| 2022 | 1560174 | 1784500 |
| 2023 | 1021994 | 1890000 |
| 2024 | 698651 | 2251000 |
| 2025 | 1542517 | 1742000 |
| 2026 | 1416987 | 1950000 |
| 2027 | 1476591 | 1930000 |

| | | |
|------|---------|---------|
| 2028 | 1840273 | 1930000 |
| 2029 | 1405843 | 1930000 |
| 2030 | 2374275 | 1930000 |
| 2031 | 2950594 | 1980000 |
| 2032 | 3976775 | 1980000 |
| 2033 | 1257682 | 1980000 |
| 2034 | 2225334 | 1980000 |
| 2035 | 7893870 | 1980000 |
| 2036 | 581479 | 1980000 |
| 2037 | 2578268 | 1980000 |
| 2038 | 1913635 | 1980000 |
| 2039 | 1869757 | 1980000 |

D.4 –Renewal Plan

Proposed renewals are included with acquisitions in the detailed construction programs included below:

CAPITAL WORKS PLAN DRAFT 20-21

| | Original 2020-21 | Adapted 2020-21 | 2021-22 | 2022-23 | 2023-24 | 2024-25 | 2025-26 |
|---|---------------------|--------------------|---------|---------|---------|---------|---------|
| KERB & GUTTER | | | | | | | |
| KERB & GUTTER INCOME | | | | | | | |
| BAROOGA | | | | | | | |
| Snell Rd - Arramagong to McKinley | 2000 | 2000 | 0 | 0 | 0 | 0 | 0 |
| Snell Rd - Kamarooka to Chomley | 35000 | 35000 | 0 | 0 | 0 | 0 | 0 |
| BAROOGA Total | 37000 | 37000 | 0 | 0 | 0 | 0 | 0 |
| BERRIGAN | | | | | | | |
| Horsfall St - Jerilderie to Denison | 12000 | 0 | 12000 | 0 | 0 | 0 | 0 |
| Barooga St - Horsfall to Nangunia St | 0 | 0 | 0 | 28000 | 0 | 0 | 0 |
| Nangunia St - Jerilderie to Barooga St | 0 | 0 | 0 | 0 | 7000 | 0 | 0 |
| Barooga St - Nangunia to Orr St | 0 | 0 | 0 | 28000 | 0 | 0 | 0 |
| Denison St - Horsfall to Nangunia West side | 0 | 0 | 0 | 0 | 0 | 28000 | 0 |
| Denison St -Nangunia to Orr St - West Side | 0 | 0 | 0 | 0 | 0 | 0 | 28000 |
| BERRIGAN Total | 12000 | 0 | 12000 | 56000 | 7000 | 28000 | 28000 |
| FINLEY | | | | | | | |
| Murray St - Wollamai Sth | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Dawe Ave - Full Length | 7000 | 7000 | 0 | 0 | 0 | 0 | 0 |
| McCallister St - Headford St to Osborne St | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| FINLEY Total | 7000 | 7000 | 0 | 0 | 0 | 0 | 0 |
| TOCUMWAL | | | | | | | |

| | | | | | | | |
|--|--------|--------|--------|--------|--------|-------|-------|
| Bruton St - End existing kerb to Bruce Birrell Dr north side | 0 | 0 | 0 | 0 | 17000 | 0 | 0 |
| Barooga St - Murray to Morris | 12000 | 12000 | 0 | 0 | 0 | 0 | 0 |
| Bruton St - Barooga St Nth to Charlotte - Sth side | 0 | 0 | 0 | 21000 | 0 | 0 | 0 |
| Hannah St - Calaway to end existing | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Emily St - Lane 960 to Hennessy | 0 | 0 | 10000 | 0 | 0 | 0 | 0 |
| Calaway St - Emily to Charlotte (bs) | 0 | 0 | 0 | 30000 | 0 | 0 | 0 |
| Charlotte St - Hennessy to Kelly | 0 | 0 | 0 | 0 | 20000 | 0 | 0 |
| Hennessy St - South side Jerilderie to Emily | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Hill St - Stabilise Pavement & Repair Kerb | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| TOCUMWAL Total | 12000 | 12000 | 10000 | 51000 | 37000 | 0 | 0 |
| UNGROUPED | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| UNGROUPED Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| KERB & GUTTER INCOME Total | 68000 | 56000 | 22000 | 107000 | 44000 | 28000 | 28000 |
| KERB & GUTTER EXPENDITURE | | | | | | | |
| BAROOGA | | | | | | | |
| Snell Rd - Arramagong to McKinley | -12000 | -12000 | 0 | 0 | 0 | 0 | 0 |
| Snell Rd - Kamarooka to Chomley | -63000 | -63000 | 0 | 0 | 0 | 0 | 0 |
| BAROOGA Total | -75000 | -75000 | 0 | 0 | 0 | 0 | 0 |
| BERRIGAN | | | | | | | |
| Horsfall St - Jerilderie to Denison | -65000 | 0 | -65000 | 0 | 0 | 0 | 0 |
| Barooga St - Horsfall to Nangunia St | 0 | 0 | 0 | -60000 | 0 | 0 | 0 |
| Nangunia St - Jerilderie to Barooga St | 0 | 0 | 0 | 0 | -32000 | 0 | 0 |
| Barooga St - Nangunia to Orr St | 0 | 0 | 0 | -60000 | 0 | 0 | 0 |
| Corcoran St - Drainage improvements | 0 | 0 | 0 | -10000 | 0 | 0 | 0 |

| | | | | | | | |
|--|--------|--------|--------|---------|---------|---------|--------|
| Denison St - Horsfall to Nangunia West side | 0 | 0 | 0 | 0 | 0 | -60000 | 0 |
| Denison St -Nangunia to Orr St - West Side | 0 | 0 | 0 | 0 | 0 | 0 | -60000 |
| BERRIGAN Total | -65000 | 0 | -65000 | -130000 | -32000 | -60000 | -60000 |
| FINLEY | | | | | | | |
| Tocumwal St Tuppal St to Wollamai St | 0 | 0 | 0 | 0 | 0 | 0 | -60000 |
| Dawe Ave - Full Length | -50000 | -50000 | 0 | 0 | 0 | 0 | 0 |
| Denison St - Ulupna to Tongs inc Median Treatment | 0 | 0 | 0 | 0 | 0 | -300000 | 0 |
| McCallister St - Headford St to Osborne St | 0 | 0 | -80000 | 0 | 0 | 0 | 0 |
| FINLEY Total | -50000 | -50000 | -80000 | 0 | 0 | -300000 | -60000 |
| TOCUMWAL | | | | | | | |
| Deniliquin Rd - Replace brick K&G Cowley to Duff ST | 0 | 0 | 0 | 0 | 0 | | |
| Barooga St - Murray to Morris | -60000 | -60000 | 0 | 0 | 0 | 0 | 0 |
| Bruton St - End existing kerb to Bruce Birrell Dr north side | 0 | 0 | 0 | 0 | -40000 | 0 | 0 |
| Bruton St - Barooga St Nth to Charlotte - Sth side | 0 | 0 | 0 | -60000 | 0 | 0 | 0 |
| Jerilderie St Nth - Connect to Bruton St | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Hannah St - Calaway to end existing | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Emily St - Lane 960 to Hennessy | 0 | 0 | -44000 | 0 | 0 | 0 | 0 |
| Emily St - Falkiner to Hennessy (east) | 0 | 0 | -15000 | 0 | 0 | 0 | 0 |
| Calaway St - Emily to Charlotte (bs) | 0 | 0 | 0 | -63000 | 0 | 0 | 0 |
| Charlotte St - Hennessy to Kelly | 0 | 0 | 0 | 0 | -70000 | 0 | 0 |
| Hennessy St - South side Jerilderie to Emily | 0 | 0 | 0 | 0 | -90000 | 0 | 0 |
| Hill St - Repair and Realign Kerb - Reconstruct Shoulder | 0 | 0 | -40000 | 0 | 0 | 0 | 0 |
| TOCUMWAL Total | -60000 | -60000 | -99000 | -123000 | -200000 | 0 | 0 |
| UNGROUPEd | | | | | | | |
| Repair existing kerb and shoulder | 0 | 0 | 0 | -40000 | -40000 | -40000 | -40000 |
| UNGROUPEd Total | 0 | 0 | 0 | -40000 | -40000 | -40000 | -40000 |

| | | | | | | | |
|---|---------|---------|---------|---------|---------|---------|---------|
| KERB & GUTTER EXPENDITURE Total | -250000 | -185000 | -244000 | -293000 | -272000 | -400000 | -160000 |
| KERB & GUTTER TOTAL | -182000 | -129000 | -222000 | -186000 | -228000 | -372000 | -132000 |
| SHIRE ROADS | | | | | | | |
| URBAN ROADS CONSTRUCTION INCOME | | | | | | | |
| BAROOGA | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| BAROOGA Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| BERRIGAN | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| BERRIGAN Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| FINLEY | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| FINLEY Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| TOCUMWAL | | | | | | | |
| Transfer from Works Reserve - Jersey St - TOC Upgrades | 0 | 0 | 0 | 0 | 0 | | |
| TOCUMWAL Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| URBAN ROADS CONSTRUCTION INCOME Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| URBAN ROADS CONSTRUCTION EXPENDITURE | | | | | | | |
| BAROOGA | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| Snell Rd - Arramagong to McKinley | -5000 | -5000 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | |
|--|---------|---------|---------|---------|--------|---------|--------|
| Snell Rd - Kamarooka to Chomley | -80000 | -80000 | 0 | 0 | 0 | 0 | 0 |
| BAROOGA Total | -85000 | -85000 | 0 | 0 | 0 | 0 | 0 |
| BERRIGAN | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| Horsfall St - Jerilderie to Denison | -90000 | 0 | -90000 | 0 | 0 | 0 | 0 |
| Barooga St - Horsfall to Nangunia St | 0 | 0 | 0 | -40000 | 0 | 0 | 0 |
| Nangunia St - Jerilderie to Barooga St | 0 | 0 | 0 | 0 | -16000 | 0 | 0 |
| Barooga St - Nangunia to Orr St | 0 | 0 | 0 | -40000 | 0 | 0 | 0 |
| Denison St - Horsfall to Nangunia West side | 0 | 0 | 0 | 0 | 0 | -40000 | 0 |
| Denison St -Nangunia to Orr St - West Side | 0 | 0 | 0 | 0 | 0 | 0 | -40000 |
| Corcoran St - Drainage improvements | | | | -29000 | | | |
| Drohan St - Construct & Seal - Lysaght to Hayes | 0 | 0 | -50000 | 0 | 0 | 0 | 0 |
| BERRIGAN Total | -90000 | 0 | -140000 | -109000 | -16000 | -40000 | -40000 |
| FINLEY | | | | | | | |
| Murray St - Wollamai Sth (drainage) | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Dawe Ave - Full Length | -150000 | -150000 | 0 | 0 | 0 | 0 | 0 |
| McCallister St - Headford St to Osborne St | 0 | 0 | -70000 | 0 | 0 | 0 | 0 |
| Tocumwal St Tuppal St to Wollamai St | 0 | 0 | 0 | 0 | 0 | 0 | -40000 |
| Coree St - Ulupna to Tongs Median Treatment | -24000 | -476253 | 0 | 0 | 0 | 0 | 0 |
| Denison St - Ulupna to Tongs inc Median Treatment | 0 | 0 | 0 | 0 | 0 | -475000 | 0 |
| FINLEY Total | -174000 | -626253 | -70000 | 0 | 0 | -475000 | -40000 |
| TOCUMWAL | | | | | | | |
| Bruton St - Barooga St Nth to Charlotte - Sth side | 0 | 0 | 0 | -120000 | 0 | 0 | 0 |
| Bruton St - End existing kerb to Bruce Birrell Dr north side | 0 | 0 | 0 | 0 | -80000 | 0 | 0 |
| Barooga St - Murray to Morris | -95000 | -95000 | 0 | 0 | 0 | 0 | 0 |
| Town Beach Road - Construct & Seal | 0 | 0 | 0 | 0 | 0 | | |

| | | | | | | | |
|--|---------|---------|---------|---------|---------|---------|---------|
| Jerilderie St Nth - Connect to Bruton St | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Hannah St - Calaway to end existing | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Emily St - Lane 960 to Hennessy | 0 | 0 | -18000 | 0 | 0 | 0 | 0 |
| Emily St - Falkiner to Hennessy (east) | 0 | 0 | -5000 | 0 | 0 | 0 | 0 |
| Calaway St - Emily to Charlotte (bs) | 0 | 0 | 0 | -25000 | 0 | 0 | 0 |
| Hennessy St - South side Jerilderie to Emily | 0 | 0 | 0 | 0 | -120000 | 0 | 0 |
| Charlotte St - Hennessy to Kelly | 0 | 0 | 0 | 0 | -140000 | 0 | 0 |
| Repair existing kerb and shoulder Hill St - Repair and Realign Kerb - Reconstruct Shoulder | 0 | 0 | -35000 | 0 | 0 | 0 | 0 |
| TOCUMWAL Total | -95000 | -95000 | -58000 | -145000 | -340000 | 0 | 0 |
| UNGROUPED | | | | | | | |
| Repair existing kerb and shoulder | 0 | 0 | 0 | -60000 | -60000 | -60000 | -60000 |
| UNGROUPED Total | 0 | 0 | 0 | -60000 | -60000 | -60000 | -60000 |
| URBAN ROADS CONSTRUCTION EXPENDITURE Total | -444000 | -806253 | -268000 | -314000 | -416000 | -575000 | -140000 |
| URBAN ROADS - RESEALS EXPENDITURE | | | | | | | |
| CHANTER ST 771 - 833 (Park Lanes) | 0 | -1000 | 0 | 0 | 0 | 0 | 0 |
| SCOULLAR ST 980 - 1028 | 0 | 0 | -1000 | 0 | 0 | 0 | 0 |
| SCOULLAR ST 926 - 980 | 0 | 0 | -1000 | 0 | 0 | 0 | 0 |
| HILL ST 393 - 494 (Reco?) | 0 | -5268 | 0 | 0 | 0 | 0 | 0 |
| HILL ST 70 - 392 (Reco?) | 0 | -15245 | 0 | 0 | 0 | 0 | 0 |
| HILL ST 00 - 70 (Reco?) | 0 | -4000 | 0 | 0 | 0 | 0 | 0 |
| MCALLISTER ST 216 - 679 (Reco?) | 0 | -5000 | 0 | 0 | 0 | 0 | 0 |
| TOCUMWAL ST 944 - 1173 (Reco?) | 0 | -13995 | 0 | 0 | 0 | 0 | 0 |
| WILLIAM ST BER 155 - 321 | 0 | 0 | 0 | -5000 | 0 | 0 | 0 |
| DENISON ST 702 - 937 | 0 | -12000 | 0 | 0 | 0 | 0 | 0 |
| DENISON ST 937 - 1409 | 0 | -17323 | 0 | 0 | 0 | 0 | 0 |
| MURRAY ST 1725 - 2025 (Park Lane) | 0 | -15000 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | |
|---------------------------|---|--------|--------|-------|---|--------|---|
| BARKER ST 263 - 402 | 0 | 0 | -6500 | 0 | 0 | 0 | 0 |
| BURMA RD 00 - 1311 | 0 | 0 | 0 | 0 | 0 | -21000 | 0 |
| MURRAY ST 220 - 460 | 0 | -8000 | 0 | 0 | 0 | 0 | 0 |
| MURRAY ST 460 - 690 | 0 | -3930 | 0 | 0 | 0 | 0 | 0 |
| AMAROO AVE 00 - 216 | 0 | -5500 | 0 | 0 | 0 | 0 | 0 |
| AMAROO AVE 216 - 456 | 0 | -5500 | 0 | 0 | 0 | 0 | 0 |
| BANKER ST 00 - 124 | 0 | -6000 | 0 | 0 | 0 | 0 | 0 |
| BANKER ST 124 - 262 | 0 | -8000 | 0 | 0 | 0 | 0 | 0 |
| BARINYA ST 392 - 839 | 0 | -11000 | 0 | 0 | 0 | 0 | 0 |
| BARKER ST 00 - 130 | 0 | 0 | -4000 | 0 | 0 | 0 | 0 |
| BARKER ST 130 - 187 | 0 | 0 | -5000 | 0 | 0 | 0 | 0 |
| BARKER ST 187 - 263 | 0 | 0 | -5000 | 0 | 0 | 0 | 0 |
| BERRIGAN RD 00 - 303 | 0 | 0 | 0 | -5000 | 0 | 0 | 0 |
| BURTON ST 00 - 88 | 0 | -4500 | 0 | 0 | 0 | 0 | 0 |
| CHARLOTTE ST 323 - 463 | 0 | 0 | -3500 | 0 | 0 | 0 | 0 |
| DAVIS ST 527 - 668 | 0 | 0 | -12000 | 0 | 0 | 0 | 0 |
| DAVIS ST 296 - 527 | 0 | 0 | -26000 | 0 | 0 | 0 | 0 |
| DENILQUIN ST 585 - 823 | 0 | -12000 | 0 | 0 | 0 | 0 | 0 |
| DENILQUIN ST 1302 - 1498 | 0 | 0 | -7000 | 0 | 0 | 0 | 0 |
| DENISON ST 1409 - 1619 | 0 | -13000 | 0 | 0 | 0 | 0 | 0 |
| DENISON ST BER 217 - 1242 | 0 | 0 | -5000 | 0 | 0 | 0 | 0 |
| ENDEAVOUR ST 00 - 391 | 0 | 0 | -8000 | 0 | 0 | 0 | 0 |
| HAMPDEN ST 617 - 647 | 0 | 0 | -2000 | 0 | 0 | 0 | 0 |
| HILES CRT 00 - 88 | 0 | 0 | -2500 | 0 | 0 | 0 | 0 |
| HORSFALL ST 00 - 134 | 0 | -2200 | 0 | 0 | 0 | 0 | 0 |
| HORSFALL ST 134 - 277 | 0 | -2300 | 0 | 0 | 0 | 0 | 0 |
| LAWSON DRIVE 00 - 129 | 0 | 0 | -6000 | 0 | 0 | 0 | 0 |
| MACDONALD CRT 00 - 105 | 0 | 0 | -3000 | 0 | 0 | 0 | 0 |
| MCALLISTER ST 679 - 914 | 0 | -8000 | 0 | 0 | 0 | 0 | 0 |
| MCFARLAND ST 175 - 405 | 0 | -10000 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | |
|--------------------------|---|--------|--------|--------|---|---|---|
| MCFARLAND ST 00 - 175 | 0 | -5000 | 0 | 0 | 0 | 0 | 0 |
| MURRAY ST 2025 - 2085 | 0 | 0 | -2000 | 0 | 0 | 0 | 0 |
| STILLARDS CRT 00 - 186 | 0 | 0 | -7000 | 0 | 0 | 0 | 0 |
| TONGS ST 1017 - 1152 | 0 | 0 | -3000 | 0 | 0 | 0 | 0 |
| WELLS ST 1008 - 1295 | 0 | 0 | -6000 | 0 | 0 | 0 | 0 |
| WOLLAMAI ST 00 - 116 | 0 | -8000 | 0 | 0 | 0 | 0 | 0 |
| WOLLAMAI ST 116 - 329 | 0 | -11000 | 0 | 0 | 0 | 0 | 0 |
| WOLLAMAI ST 329 - 402 | 0 | -20000 | 0 | 0 | 0 | 0 | 0 |
| WOLLAMAI ST 402 - 552 | 0 | -16000 | 0 | 0 | 0 | 0 | 0 |
| BAROOGA ST 00 - 506 | 0 | 0 | 0 | -17000 | 0 | 0 | 0 |
| BRUTON ST 1126 - 1264 | 0 | 0 | -6000 | 0 | 0 | 0 | 0 |
| BRUTON ST 1040 - 1126 | 0 | 0 | -4000 | 0 | 0 | 0 | 0 |
| BUCHANANS RD 1500 - 1887 | 0 | 0 | -10000 | 0 | 0 | 0 | 0 |
| CLOSE ST 00 - 100 | 0 | 0 | -5000 | 0 | 0 | 0 | 0 |
| COBRAM ST TOC 516 - 612 | 0 | 0 | -2500 | 0 | 0 | 0 | 0 |
| COBRAM ST TOC 275 - 413 | 0 | 0 | -2500 | 0 | 0 | 0 | 0 |
| COBRAM ST TOC 413 - 516 | 0 | 0 | -5000 | 0 | 0 | 0 | 0 |
| DAWE AVE 253 - 576 | 0 | 0 | -13000 | 0 | 0 | 0 | 0 |
| DAWE AVE 00 - 253 | 0 | 0 | -12000 | 0 | 0 | 0 | 0 |
| GUNNAMARA ST 121 - 346 | 0 | 0 | -10000 | 0 | 0 | 0 | 0 |
| HOYLE ST 00 - 216 | 0 | 0 | -6000 | 0 | 0 | 0 | 0 |
| KAMAROOKA ST 475 - 788 | 0 | 0 | -7000 | 0 | 0 | 0 | 0 |
| TUPPAL ST 630 - 684 | 0 | 0 | -4000 | 0 | 0 | 0 | 0 |
| WISE CRT 00 - 275 | 0 | 0 | -10000 | 0 | 0 | 0 | 0 |
| BUCHANANS RD 866 - 900 | 0 | 0 | -2000 | 0 | 0 | 0 | 0 |
| BURKE ST 00 - 243 | 0 | 0 | 0 | -6000 | 0 | 0 | 0 |
| CLOSE ST 100 - 236 | 0 | 0 | -5500 | 0 | 0 | 0 | 0 |
| CORCORAN ST 00 - 382 | 0 | 0 | -16000 | 0 | 0 | 0 | 0 |
| COREE ST 00 - 245 | 0 | 0 | 0 | -14000 | 0 | 0 | 0 |
| DEAN ST EAST 00 - 190 | 0 | 0 | -9000 | 0 | 0 | 0 | 0 |

| | | | | | | | |
|--------------------------|---|--------|--------|--------|--------|---|---|
| DENISON ST BER 00 - 217 | 0 | 0 | -8000 | 0 | 0 | 0 | 0 |
| DRUITT CRT 00 - 86 | 0 | 0 | 0 | -2500 | 0 | 0 | 0 |
| ENDEAVOUR ST 391 - 673 | 0 | 0 | -8000 | 0 | 0 | 0 | 0 |
| FORREST CRT 00 - 57 | 0 | 0 | 0 | -2000 | 0 | 0 | 0 |
| GORMLEY CRT 00 - 195 | 0 | 0 | 0 | -4500 | 0 | 0 | 0 |
| GREGGERYS RD 198 - 396 | 0 | 0 | -7000 | 0 | 0 | 0 | 0 |
| GUNNAMARA ST 00 - 121 | 0 | 0 | -6000 | 0 | 0 | 0 | 0 |
| JAMES CRT 00 - 196 | 0 | 0 | 0 | -6000 | 0 | 0 | 0 |
| KELLY ST 439 - 664 | 0 | 0 | 0 | -3000 | 0 | 0 | 0 |
| KELLY ST 664 - 801 | 0 | 0 | 0 | -4000 | 0 | 0 | 0 |
| KELLY ST 801 - 948 | 0 | 0 | 0 | -2000 | 0 | 0 | 0 |
| KELLY ST 948 - 1030 | 0 | 0 | 0 | -2500 | 0 | 0 | 0 |
| LANE NO 840 809 - 1039 | 0 | 0 | 0 | -3500 | 0 | 0 | 0 |
| MURRAY ST 690 - 920 | 0 | 0 | -11000 | 0 | 0 | 0 | 0 |
| TOCUMWAL ST 372 - 715 | 0 | -23000 | 0 | 0 | 0 | 0 | 0 |
| TOCUMWAL ST 242 - 372 | 0 | 0 | 0 | 0 | -9000 | 0 | 0 |
| TOCUMWAL ST 00 - 242 | 0 | 0 | 0 | -11000 | 0 | 0 | 0 |
| TONGS ST 912 - 1017 | 0 | 0 | 0 | -3500 | 0 | 0 | 0 |
| TONGS ST 386 - 912 | 0 | 0 | 0 | -19500 | 0 | 0 | 0 |
| TOWN BEACH RD 00 - 110 | 0 | 0 | 0 | -2000 | 0 | 0 | 0 |
| TUPPAL ST 684 - 914 | 0 | 0 | 0 | -8000 | 0 | 0 | 0 |
| WILLIAM ST 289 - 376 | 0 | 0 | -2000 | 0 | 0 | 0 | 0 |
| WILLIAM ST BER 00 - 155 | 0 | 0 | 0 | double | 0 | 0 | 0 |
| WILLIAM ST BER 321 - 399 | 0 | 0 | -3000 | 0 | 0 | 0 | 0 |
| WOLLAMAI ST 1497 - 1599 | 0 | 0 | 0 | 0 | -3000 | 0 | 0 |
| WOLLAMAI ST 1282 - 1497 | 0 | 0 | 0 | 0 | -11000 | 0 | 0 |
| ADAMS ST 70 - 195 | 0 | 0 | 0 | 0 | -7000 | 0 | 0 |
| ADAMS ST 00 - 30 | 0 | 0 | 0 | 0 | -2000 | 0 | 0 |
| ADAMS ST 30 - 70 | 0 | 0 | 0 | 0 | -3000 | 0 | 0 |
| ALEXANDER AVE 00 - 286 | 0 | 0 | 0 | -12000 | 0 | 0 | 0 |

| | | | | | | | |
|--------------------------|---|--------|-------|-------|--------|--------|---|
| ANTHONY AVE 00 - 151 | 0 | 0 | 0 | 0 | 0 | -3000 | 0 |
| BARINYA ST 00 - 392 | 0 | 0 | 0 | 0 | -14000 | 0 | 0 |
| BERRIGAN ST 00 - 266 | 0 | 0 | 0 | 0 | 0 | -7000 | 0 |
| CARTER ST 00 - 258 | 0 | 0 | 0 | -9000 | 0 | 0 | 0 |
| CHANTER ST 341 - 771 | 0 | 0 | 0 | 0 | -8000 | 0 | 0 |
| COWLEY ST 00 - 150 | 0 | 0 | 0 | 0 | -4500 | 0 | 0 |
| DUFF ST 00 - 104 | 0 | 0 | 0 | 0 | -4500 | 0 | 0 |
| HILLSON ST 00 - 88 | 0 | 0 | 0 | 0 | 0 | -3000 | 0 |
| ISABEL AVE 00 - 101 | 0 | 0 | 0 | 0 | -3500 | 0 | 0 |
| LAWSON DRIVE 129 - 295 | 0 | 0 | 0 | 0 | 0 | -5000 | 0 |
| LAWSON DRIVE 295 - 532 | 0 | 0 | -9000 | 0 | 0 | 0 | 0 |
| LORELLE CRT 00 - 71 | 0 | 0 | 0 | 0 | 0 | -1000 | 0 |
| LORELLE CRT 71 - 136 | 0 | 0 | 0 | 0 | 0 | -1000 | 0 |
| MURRAY ST NTH 127 - 1030 | 0 | 0 | 0 | 0 | -19000 | 0 | 0 |
| PARKES ST 00 - 234 | 0 | 0 | 0 | 0 | 0 | -10000 | 0 |
| RILEY COURT A 265 - 304 | 0 | 0 | 0 | 0 | -1000 | 0 | 0 |
| RILEY COURT A 304 - 310 | 0 | 0 | 0 | 0 | -1000 | 0 | 0 |
| RILEY CRT 103 - 265 | 0 | 0 | 0 | 0 | -3000 | 0 | 0 |
| SCOULLAR ST 256 - 340 | 0 | 0 | 0 | 0 | 0 | -2000 | 0 |
| SHORT ST A 00 - 59 | 0 | 0 | 0 | 0 | 0 | -1000 | 0 |
| WOLLAMAI ST 552 - 665 | 0 | 0 | -9000 | 0 | 0 | 0 | 0 |
| WOLLAMAI ST 728 - 822 | 0 | 0 | 0 | 0 | 0 | -7000 | 0 |
| CALAWAY ST 696 - 914 | 0 | 0 | 0 | 0 | -6000 | 0 | 0 |
| FINLEY ST 480 - 713 | 0 | 0 | 0 | 0 | -12000 | 0 | 0 |
| GOLFCOURSE RD 00 - 150 | 0 | 0 | 0 | 0 | 0 | -7500 | 0 |
| HUTSONS RD 00 - 941 | 0 | -20000 | 0 | 0 | 0 | 0 | 0 |
| MURRAY GROVE 00 - 285 | 0 | 0 | 0 | 0 | -6000 | 0 | 0 |
| PINNUCK ST 00 - 246 | 0 | 0 | 0 | 0 | 0 | -5000 | 0 |
| PINNUCK ST 246 - 302 | 0 | 0 | 0 | 0 | 0 | -3000 | 0 |
| PINNUCK ST 302 - 732 | 0 | 0 | 0 | 0 | 0 | -25000 | 0 |

| | | | | | | | |
|--------------------------|---|---|---|--------|-------|--------|--------|
| PINNUCK ST 732 - 976 | 0 | 0 | 0 | 0 | 0 | -14000 | 0 |
| ULUPNA ST 00 - 411 | 0 | 0 | 0 | 0 | 0 | -33000 | 0 |
| BRIDGE ST 298 - 436 | 0 | 0 | 0 | 0 | 0 | 0 | -3000 |
| COLLIE ST 698 - 915 | 0 | 0 | 0 | 0 | 0 | -6500 | 0 |
| FLIGHT PLACE 00 - 202 | 0 | 0 | 0 | 0 | 0 | -4000 | 0 |
| HEADFORD ST 452 - 710 | 0 | 0 | 0 | 0 | 0 | 0 | -9000 |
| HENNESSY ST 250 - 291 | 0 | 0 | 0 | 0 | 0 | -1000 | 0 |
| HENNESSY ST 00 - 250 | 0 | 0 | 0 | 0 | 0 | -3000 | 0 |
| HONNIBALL DR 00 - 325 | 0 | 0 | 0 | -6000 | 0 | 0 | 0 |
| HONNIBALL DR 325 - 1101 | 0 | 0 | 0 | -13000 | 0 | 0 | 0 |
| INGO RENER DR 00 - 257 | 0 | 0 | 0 | 0 | 0 | -7800 | 0 |
| JERILDERIE ST 580 - 831 | 0 | 0 | 0 | 0 | 0 | -8000 | 0 |
| JERILDERIE ST 831 - 1120 | 0 | 0 | 0 | 0 | -9000 | 0 | 0 |
| SCOULLAR ST 748 - 926 | 0 | 0 | 0 | 0 | 0 | 0 | -4000 |
| TONGS ST 1152 - 1322 | 0 | 0 | 0 | 0 | 0 | -9000 | 0 |
| TOWN BEACH RD 110 - 361 | 0 | 0 | 0 | 0 | 0 | 0 | -2000 |
| ANTHONY AVE 151 - 337 | 0 | 0 | 0 | 0 | -4000 | 0 | 0 |
| BABS CRT 00 - 311 | 0 | 0 | 0 | 0 | 0 | -7500 | 0 |
| BANKER ST 536 - 879 | 0 | 0 | 0 | 0 | 0 | 0 | -7000 |
| BRIDGET ST 00 - 300 | 0 | 0 | 0 | 0 | 0 | 0 | -13000 |
| BROOKS AVE 00 - 139 | 0 | 0 | 0 | 0 | 0 | 0 | -4000 |
| BROOKS AVE 139 - 209 | 0 | 0 | 0 | 0 | 0 | 0 | -2000 |
| BROOKS AVE 209 - 376 | 0 | 0 | 0 | 0 | 0 | 0 | -5000 |
| BRUNKER ST 344 - 513 | 0 | 0 | 0 | 0 | -4500 | 0 | 0 |
| BRUTON ST 1264 - 1440 | 0 | 0 | 0 | 0 | 0 | 0 | -9000 |
| BRUTON ST 00 - 591 | 0 | 0 | 0 | 0 | 0 | 0 | -23000 |
| CALAWAY ST 356 - 458 | 0 | 0 | 0 | 0 | 0 | 0 | -3000 |
| CHARLOTTE ST 00 - 149 | 0 | 0 | 0 | 0 | 0 | 0 | -6000 |
| CHARLOTTE ST 146 - 323 | 0 | 0 | 0 | 0 | 0 | 0 | -7000 |
| CLAIRE DR 00 - 508 | 0 | 0 | 0 | 0 | 0 | 0 | -10000 |

| | | | | | | | |
|---|---|---------|---------|---------|---------|---------|---------|
| CORCORAN ST 522 - 723 | 0 | 0 | 0 | 0 | 0 | 0 | -7000 |
| COWLEY ST 150 - 220 | 0 | 0 | 0 | 0 | -2500 | 0 | 0 |
| CREED ST 00 - 157 | 0 | 0 | 0 | 0 | 0 | 0 | -6000 |
| FOUNDRY LANE 1039 - 1274 | 0 | 0 | 0 | 0 | 0 | 0 | -3000 |
| GEORGE ST 00 - 122 | 0 | 0 | 0 | 0 | 0 | -3000 | 0 |
| GREGGERYS RD 516 - 725 | 0 | 0 | 0 | -4500 | 0 | 0 | 0 |
| HAMPDEN ST 250 - 617 | 0 | 0 | 0 | 0 | 0 | 0 | -16000 |
| HAMPDEN ST 65 - 250 | 0 | 0 | 0 | 0 | 0 | 0 | -10000 |
| HANNAH ST 00 - 287 | 0 | 0 | 0 | 0 | 0 | 0 | -12000 |
| JAMES CRT TOC 00 - 228 | 0 | 0 | 0 | 0 | 0 | -5500 | 0 |
| LYSAGHT ST 00 - 405 | 0 | 0 | 0 | 0 | -11000 | 0 | 0 |
| MOORE ST 00 - 526 | 0 | 0 | 0 | 0 | 0 | -15000 | 0 |
| NANGUNIA ST BER 00 - 492 | 0 | 0 | 0 | 0 | 0 | -11000 | 0 |
| PINE VIEW DR 00 - 427 | 0 | 0 | 0 | 0 | 0 | -10500 | 0 |
| URBAN ROADS - RESEALS EXPENDITURE Total | 0 | -291761 | -308000 | -165500 | -148500 | -240300 | -161000 |
| TOWNSCAPE WORKS INCOME | | | | | | | |
| BAROOGA | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| BAROOGA Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| BERRIGAN | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| BERRIGAN Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| FINLEY | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| FINLEY Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | |
|---|---------|--------|---------|---------|---------|---|---|
| TOCUMWAL | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| TOCUMWAL Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| TOWNSCAPE WORKS INCOME Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| TOWNSCAPE WORKS EXPENDITURE | | | | | | | |
| BAROOGA | | | | | | | |
| Town Entry | 0 | 0 | 0 | 0 | 0 | | |
| BAROOGA Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| BERRIGAN | | | | | | | |
| Town Entry | 0 | 0 | 0 | 0 | 0 | | |
| BERRIGAN Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| FINLEY | | | | | | | |
| Coree St - Ulupna to Tongs Median Treatment | -50000 | 0 | -50000 | -50000 | 0 | | |
| Denison St - Ulupna to Tongs Median Treatment | 0 | 0 | 0 | 0 | -50000 | | |
| FINLEY Total | -50000 | 0 | -50000 | -50000 | -50000 | 0 | 0 |
| TOCUMWAL | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| TOCUMWAL Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| UNGROUPED | | | | | | | |
| Town Entry | -100000 | -50000 | -100000 | -100000 | -100000 | | |
| UNGROUPED Total | -100000 | -50000 | -100000 | -100000 | -100000 | 0 | 0 |
| TOWNSCAPE WORKS EXPENDITURE Total | -150000 | -50000 | -150000 | -150000 | -150000 | 0 | 0 |

| | | | | | | | |
|--|---------|---------|------------|----------|----------|----------|---|
| TOWNSCAPE WORKS TOTAL | -150000 | -50000 | -150000 | -150000 | -150000 | 0 | 0 |
| RURAL ROADS UNSEALED - RESHEET INCOME | | | | | | | |
| UNGROUPED | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| UNGROUPED Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| RURAL ROADS UNSEALED - RESHEET INCOME Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| RURAL ROADS UNSEALED - RESHEET EXPENDITURE | | | | | | | |
| UNGROUPED | 0 | 0 | 0 | 0 | 0 | 0 | |
| Alexanders Rd From End of Bitumen to Old Toc Berrigan Rd | -70000 | -70000 | 0 | 0 | 0 | 0 | 0 |
| Womboin RdMR363 to Nolans Rd - 3150 | 0 | 0 | -115083.4 | 0 | 0 | 0 | 0 |
| Womboin RdMR550 to Kennedy's Rd - 3350 | 0 | 0 | -121896.92 | 0 | 0 | 0 | 0 |
| MIECHELS RD0 to 3040 - 3040 | 0 | 0 | -111335.96 | 0 | 0 | 0 | 0 |
| Laffeys Rd from Ennals Rd to MIL ent - 980 | 0 | 0 | -41156.708 | 0 | 0 | 0 | 0 |
| Laffeys Rd from Ennals Rd to house entrance | -20000 | -20000 | 0 | 0 | 0 | 0 | 0 |
| Hogans Rd371 to 2459 - 2088 | 0 | 0 | -78903.609 | 0 | 0 | 0 | 0 |
| BOXWOOD RD0 to 2753 - 2753 | 0 | 0 | 0 | -101559 | 0 | 0 | 0 |
| Miechels Rd from SH17 to 3.1km West | -119000 | -119000 | 0 | 0 | 0 | 0 | 0 |
| EDNIES RD0 to 2003 - 2003 | 0 | 0 | 0 | -76007.9 | 0 | 0 | 0 |
| Winters Rd MR363 to 2.4km - 2400 | 0 | 0 | 0 | -89532.7 | 0 | 0 | 0 |
| SHERWINS RD1585 to 5313 - 3728 | 0 | 0 | 0 | -134774 | 0 | 0 | 0 |
| Winters Rd from MR363 to 1.5km East | -50000 | -50000 | 0 | 0 | 0 | 0 | 0 |
| OLD ADCOCKS RD2637 to 6026 - 3389 | 0 | 0 | 0 | 0 | -123226 | 0 | 0 |
| EARLS RD0 to 2363 - 2363 | 0 | 0 | 0 | 0 | -88272.2 | 0 | 0 |
| EDGECOMBE RD0 to 2134 - 2134 | 0 | 0 | 0 | 0 | -80470.7 | 0 | 0 |
| SULLIVANS RD0 to 2660 - 2660 | 0 | 0 | 0 | 0 | -98390.3 | 0 | 0 |
| LARKINS RD5417 to 7563 - 2146 | 0 | 0 | 0 | 0 | 0 | -80879.5 | 0 |
| MCDONALDS RD2763 to 6300 - 3537 | 0 | 0 | 0 | 0 | 0 | -128268 | 0 |

| | | | | | | | |
|--|---------|---------|--------|--------|--------|----------|----------|
| MILLS RD0 to 4849 - 4849 | 0 | 0 | 0 | 0 | 0 | -172964 | 0 |
| MORTONS RD6028 to 6686 - 658 | 0 | 0 | 0 | 0 | 0 | -30186.9 | 0 |
| Wiltons Rd3000 to 5300 - 2300 | 0 | 0 | 0 | 0 | 0 | 0 | -86125.9 |
| hogans Rd | -180000 | -180000 | 0 | 0 | 0 | 0 | 0 |
| Daltons Rd0 to 1782 - 1782 | 0 | 0 | 0 | 0 | 0 | 0 | -68478.9 |
| Thorburn Rd5113 to 9632 - 4519 | 0 | 0 | 0 | 0 | 0 | 0 | -161722 |
| Creed St157 to 407 - 250 | 0 | 0 | 0 | 0 | 0 | 0 | -16287.4 |
| cronulla Rd0 to 1495 - 1495 | 0 | 0 | 0 | 0 | 0 | 0 | -58701.5 |
| Spring Rd 300 (near Jenkins) - 300 | 0 | 0 | 0 | 0 | 0 | 0 | -17990.7 |
| urban lanes / rec | 0 | 0 | -50000 | -50000 | -50000 | -50000 | -50000 |
| Jenkins Rd0 to 1108 - 1108 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Back Barooga Rdconfirm location - 2000 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Lower River Rdconfirm location - 2000 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Clearview RdYarrowonga Rd to end - 2347 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Stonebank Rd2020/2021 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Lawlors Rd from Thorntons Rd to 1.6k | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Eastfrom Thorntons Rd to 1.6k East - 1600 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Greggerys Rd725 to 975 - 250 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Marantells RdRiverina hwt to nth 750m - 750 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ruwolts Rdsections not responsible by quarry's - 530 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Taylors Rd2270 to 6201 - 3931 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| VAGGS RD0 to 2800 - 2800 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| BROOKMANNS RD4500 to 9000 - 4500 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| CAMERONS LANE0 to 500 - 500 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| STOCK ROUTE RD6659 to 11416 - 4757 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Smithers Rd0 to 3590 - 3590 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| UNGROUPED Total | | | | | | | |

| | | | | | | | |
|--|---------|---------|-----------|---------|---------|---------|---------|
| RURAL ROADS UNSEALED - RESHEET EXPENDITURE Total | -439000 | -439000 | -518376.6 | -451874 | -440359 | -462298 | -459306 |
| RURAL ROADS SEALED - RESEALS INCOME | | | | | | | |
| UNGROUPED | | | | | | | |
| To be determined | 0 | 0 | 0 | 0 | 0 | | |
| UNGROUPED Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| RURAL ROADS SEALED - RESEALS INCOME Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| RURAL ROADS SEALED - RESEALS EXPENDITURE | | | | | | | |
| HUGHES ST 326 - 463 | 0 | 0 | 0 | 0 | -11000 | 0 | 0 |
| HUGHES ST 463 - 623 | 0 | 0 | 0 | 0 | -8000 | 0 | 0 |
| GOLFCOURSE RD 150 - 273 | 0 | 0 | 0 | 0 | 0 | -10000 | 0 |
| GOLFCOURSE RD 273 - 2063 | 0 | 0 | 0 | 0 | 0 | -90000 | 0 |
| GOLFCOURSE RD 2063 - 2955 | 0 | 0 | 0 | 0 | 0 | -45000 | 0 |
| COLDWELLS RD 6615 - 6830 | 0 | 0 | -4000 | 0 | 0 | 0 | 0 |
| COLDWELLS RD 00 - 3621 | 0 | -63000 | 0 | 0 | 0 | 0 | 0 |
| COLDWELLS RD 5395 - 6615 | 0 | 0 | -18000 | 0 | 0 | 0 | 0 |
| COLDWELLS RD 6830 - 7052 | 0 | 0 | -4000 | 0 | 0 | 0 | 0 |
| RACECOURSE RD 7322 - 7862 | 0 | -15000 | 0 | 0 | 0 | 0 | 0 |
| RACECOURSE RD BER - 00 - 1080 | 0 | -22000 | 0 | 0 | 0 | 0 | 0 |
| TUPPAL RD 1398 - 1799 | 0 | 0 | -8000 | 0 | 0 | 0 | 0 |
| WOOLSHED RD 2562 - 2819 | 0 | 0 | -4000 | 0 | 0 | 0 | 0 |
| RACECOURSE RD 4279 - 5669 | 0 | 0 | -53000 | 0 | 0 | 0 | 0 |
| LOWER RIVER RD 1902 - 2278 | 0 | 0 | -8000 | 0 | 0 | 0 | 0 |
| LOWER RIVER RD 00 - 1902 | 0 | 0 | 0 | -38000 | 0 | 0 | 0 |
| COLDWELLS RD 7052 - 8185 | 0 | 0 | 0 | -15000 | 0 | 0 | 0 |
| MELROSE RD 00 - 4948 | 0 | 0 | 0 | 0 | -150000 | 0 | 0 |
| RACECOURSE RD 00 - 1541 | 0 | 0 | -20000 | 0 | 0 | 0 | 0 |
| SOUTH COREE RD 8777 - 10395 | 0 | 0 | -36000 | 0 | 0 | 0 | 0 |

| | | | | | | | |
|---|---|--------|---------|---------|---------|---------|---------|
| TUPPAL RD 13292 - 18491 | 0 | 0 | 0 | -120000 | 0 | 0 | 0 |
| TUPPAL RD 8408 - 3290 | 0 | 0 | 0 | 0 | -150000 | 0 | 0 |
| TUPPAL RD 2852 - 4800 | 0 | 0 | 0 | 0 | -50000 | 0 | 0 |
| TUPPAL RD 4800 - 5558 | 0 | 0 | 0 | 0 | 0 | -58000 | 0 |
| YARRAWONGA RD 10495 - 12331 | 0 | 0 | 0 | 0 | -37000 | 0 | 0 |
| YARRAWONGA RD13149 - 18728 | 0 | 0 | 0 | 0 | 0 | -114000 | 0 |
| CROSBIES RD 00 - 98 | 0 | 0 | 0 | 0 | 0 | -2000 | 0 |
| CROSBIES RD 2665 - 3032 | 0 | 0 | 0 | 0 | 0 | -4000 | 0 |
| CROSBIES RD 3972 - 4421 | 0 | 0 | 0 | 0 | 0 | 0 | -8000 |
| CROSBIES RD 5692 - 5993 | 0 | 0 | 0 | 0 | 0 | -5000 | 0 |
| WOOLSHED RD 15180 - 17214 | 0 | 0 | 0 | 0 | -35000 | 0 | 0 |
| YARRAWONGA RD 7082 - 10495 | 0 | 0 | 0 | 0 | 0 | 0 | -85000 |
| YARRAWONGA RD 6490 - 7082 | 0 | 0 | 0 | 0 | 0 | -20000 | 0 |
| YARRAWONGA RD 3592 - 6490 | 0 | 0 | 0 | 0 | 0 | 0 | -65000 |
| YARRAWONGA RD2632 - 3592 | 0 | 0 | 0 | 0 | 0 | 0 | -21000 |
| YARRAWONGA RD 29403 - 30501 | 0 | 0 | 0 | 0 | 0 | 0 | -43000 |
| FULLERS RD 3400 - 6498 | 0 | 0 | 0 | 0 | 0 | 0 | -50000 |
| TUPPAL RD 879 - 1398 | 0 | 0 | 0 | 0 | 0 | 0 | -9000 |
| YARRAWONGA RD 24662 - 26084 | 0 | 0 | 0 | 0 | 0 | 0 | -55000 |
| FULLERS RD 3255 - 3400 | 0 | 0 | 0 | 0 | 0 | 0 | -5000 |
| YARRAWONGA RD 26084 - 29403 | 0 | 0 | 0 | 0 | 0 | 0 | -129000 |
| SEPPELTS RD 0 - 60 | 0 | -2000 | 0 | 0 | 0 | 0 | 0 |
| BACK BAROOGA RD 6558 - 6787 | 0 | 0 | -3000 | 0 | 0 | 0 | 0 |
| PINEY RD 4576 -5941 (Shoulder Widening) | 0 | 0 | -172500 | 0 | 0 | 0 | 0 |
| PINEY RD 5941 - 6594 | 0 | 0 | -11000 | 0 | 0 | 0 | 0 |
| BURMA RD 00 - 1311 | 0 | -25000 | 0 | 0 | 0 | 0 | 0 |
| BARNES RD 2740 - 3462 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| CARAMAR RD 622 - 5876 | 0 | 0 | 0 | 0 | 0 | -95000 | 0 |
| LOGIE BRAE RD 2379 - 2726 | 0 | -6000 | 0 | 0 | 0 | 0 | 0 |
| LOGIE BRAE RD 2726 - 5466 | 0 | -56000 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | |
|------------------------------|--------|--------|--------|--------|--------|--------|---|
| MARSHES RD 00 - 1956 | 0 | 0 | 0 | 0 | 0 | -76000 | 0 |
| PINEY RD 11377 - 13763 | 0 | -30000 | 0 | 0 | 0 | 0 | 0 |
| SHANDS RD 00 - 5718 | 0 | 0 | 0 | -72000 | 0 | 0 | 0 |
| ALEXANDERS RD 00 - 65 | 0 | 0 | -1000 | 0 | 0 | 0 | 0 |
| ALEXANDERS RD 65 - 1307 | 0 | 0 | -16000 | 0 | 0 | 0 | 0 |
| CARAMAR RD 5876 - 6160 | 0 | 0 | 0 | -7000 | 0 | 0 | 0 |
| CARAMAR RD 6160 - 6802 | 0 | 0 | 0 | -10000 | 0 | 0 | 0 |
| CASEYS RD 4960 - 5948 | 0 | 0 | -13000 | 0 | 0 | 0 | 0 |
| CLEARVIEW RD 00 - 310 | 0 | 0 | -6000 | 0 | 0 | 0 | 0 |
| DALES RD 00 - 1831 | 0 | -36000 | 0 | 0 | 0 | 0 | 0 |
| DALES RD 1871 - 2665 | 0 | -15000 | 0 | 0 | 0 | 0 | 0 |
| PINELODGE RD3086.007577.00 | 0 | 0 | -85000 | 0 | 0 | 0 | 0 |
| SPRINGFIELD RD3855.004628.00 | 0 | 0 | -10000 | 0 | 0 | 0 | 0 |
| BABBINGTONS RD841.001717.00 | 0 | 0 | 0 | -18000 | 0 | 0 | 0 |
| BURMA RD1311.002243.00 | 0 | 0 | 0 | -18000 | 0 | 0 | 0 |
| BUSHFIELD RD0.004012.00 | -22000 | 0 | 0 | -51000 | 0 | 0 | 0 |
| CASEYS RD5948.006321.00 | -29000 | 0 | 0 | 0 | -4000 | 0 | 0 |
| CASEYS RD6321.007276.00 | -72000 | 0 | 0 | 0 | -19000 | 0 | 0 |
| LAWLORS RD BER0.003572.00 | 0 | 0 | 0 | -45000 | 0 | 0 | 0 |
| MCMURRAYS RD0.001110.00 | 0 | 0 | 0 | 0 | 0 | -19000 | 0 |
| NARROW PLAINS RD0.001119.00 | 0 | 0 | 0 | -60000 | 0 | 0 | 0 |
| PEPPERTREE RD5188.005801.00 | 0 | 0 | 0 | -12000 | 0 | 0 | 0 |
| PEPPERTREE RD5801.008004.00 | 0 | 0 | 0 | -5000 | 0 | 0 | 0 |
| PEPPERTREE RD8004.008354.00 | 0 | 0 | 0 | -42000 | 0 | 0 | 0 |
| PINEY RD6594.008581.00 | 0 | 0 | 0 | -25000 | 0 | 0 | 0 |
| SEPPELTS RD60.001484.00 | 0 | -27000 | 0 | 0 | 0 | 0 | 0 |
| STOCK ROUTE RD0.002358.00 | 0 | 0 | -30000 | 0 | 0 | 0 | 0 |
| STOCK ROUTE RD2358.002707.00 | 0 | 0 | -7000 | 0 | 0 | 0 | 0 |
| STOCK ROUTE RD2707.003035.00 | 0 | 0 | -4000 | 0 | 0 | 0 | 0 |
| BATTENS RD0.00141.00 | 0 | 0 | 0 | -3000 | 0 | 0 | 0 |

| | | | | | | | |
|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| BATTENS RD143.00478.00 | 0 | 0 | 0 | -5000 | 0 | 0 | 0 |
| BATTENS RD478.00691.00 | 0 | 0 | 0 | -3000 | 0 | 0 | 0 |
| BATTENS RD691.001073.00 | 0 | 0 | 0 | -5000 | 0 | 0 | 0 |
| BATTENS RD1073.001321.00 | 0 | 0 | 0 | -4000 | 0 | 0 | 0 |
| BATTENS RD1321.004404.00 | 0 | 0 | 0 | -42000 | 0 | 0 | 0 |
| BRAYBONS RD0.003574.00 | 0 | 0 | 0 | 0 | -46000 | 0 | 0 |
| CARAMAR RD0.00622.00 | 0 | 0 | 0 | 0 | -14000 | 0 | 0 |
| CARRUTHERS RD0.001660.00 | 0 | 0 | 0 | 0 | -21000 | 0 | 0 |
| CASEYS RD7276.008371.00 | 0 | 0 | 0 | 0 | 0 | -39000 | 0 |
| HOGANS RD2459.003079.00 | 0 | 0 | 0 | 0 | -12000 | 0 | 0 |
| KILLEENS RD2386.002742.00 | 0 | 0 | 0 | -9000 | 0 | 0 | 0 |
| MARIAN DR0.00679.00 | 0 | 0 | 0 | 0 | -14000 | 0 | 0 |
| MAXWELLS RD0.005100.00 | 0 | 0 | 0 | 0 | 0 | 0 | -122000 |
| MAXWELLS RD8368.008454.00 | 0 | 0 | 0 | 0 | 0 | 0 | -1000 |
| MCCULLOCHS RD0.003043.00 | 0 | 0 | 0 | 0 | -38000 | 0 | 0 |
| NARROW PLAINS RD0.001119.00 | 0 | 0 | 0 | -20000 | 0 | 0 | 0 |
| OLD TOC BER RD4306.004932.00 | 0 | 0 | 0 | 0 | -11000 | 0 | 0 |
| PINELODGE RD0.003086.00 | 0 | 0 | 0 | 0 | -59000 | 0 | 0 |
| PINEY RD3390.004576.00 | 0 | 0 | 0 | -25000 | 0 | 0 | 0 |
| QUICKS RD TOC0.001931.00 | 0 | 0 | 0 | -39000 | 0 | 0 | 0 |
| QUIRKS RD5017.006644.00 | 0 | 0 | 0 | 0 | -21000 | 0 | 0 |
| THORBURNS RD4426.005113.00 | 0 | 0 | 0 | 0 | -9000 | 0 | 0 |
| HUESTONS RD292.004845.00 | 0 | 0 | 0 | 0 | 0 | 0 | -49000 |
| HUESTONS RD4845.008726.00 | 0 | 0 | 0 | 0 | 0 | 0 | -42000 |
| RURAL ROADS SEALED - RESEALS EXPENDITURE Total | -123000 | -297000 | -513500 | -693000 | -709000 | -577000 | -684000 |
| RURAL ROADS CONSTRUCTION INCOME | | | | | | | |

| | | | | | | | |
|---|---------|---------|---------|---------|---------|---------|---------|
| UNGROUPED | | | | | | | |
| Fixing Country Roads - Strathvale Rd | 0 | 0 | 0 | 0 | 0 | | |
| UNGROUPED Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| RURAL ROADS CONSTRUCTION INCOME Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| RURAL ROADS CONSTRUCTION EXPENDITURE | | | | | | | |
| UNGROUPED | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Barnes Rd - Logie Brae Rd to Maxwells Rd | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Barnes Rd - Maxwell Rd to South Coree Rd | 0 | 0 | 0 | -220000 | 0 | 0 | 0 |
| Battens Rd MR356 to Green Swamp Rd | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Caseys Rd 00 to 1.5km | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Clearzones | -75000 | -50000 | -50000 | -50000 | -50000 | -50000 | -50000 |
| Coldwells Rd - 5300 to 6300 east of Berrigan-Barooga Rd | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Coldwells Rd - 4965-5395 | 0 | 0 | -113000 | 0 | 0 | 0 | 0 |
| Draytons Rd - Withers Rd to Yarrawonga Rd | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Piney Rd - Bends Section | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Shands Rd - MR363 to Rockcliffs Rd | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| To be determined | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Burma Rd 00 to 1.3km | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Woolshed Rd 2.4 to 2.9 & 3.5 to 4.8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Yarrawonga Rd 2.1 to 6.1 | -560000 | -140000 | -140000 | -140000 | -140000 | 0 | 0 |
| Yarrawonga Rd 20.1 to 21.7 | 0 | 0 | -225000 | 0 | 0 | 0 | 0 |
| Yarrawonga Rd 00-733 | 0 | 0 | 0 | 0 | 0 | 0 | -174000 |
| Maxwells Rd - 5.7 to 7.4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Piney Rd - 11.8 to 13.8 | 0 | 0 | 0 | 0 | 0 | -250000 | 0 |
| Bushfield Rd 00 to 5km | -355174 | -355174 | -250000 | 0 | 0 | 0 | 0 |
| Yarrawonga Rd 18.7 to 21.7 | -100000 | -100000 | 0 | 0 | 0 | 0 | 0 |
| Peppertree Rd - to 3.5 to 4.2 from woolshed | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Crosbies Rd Bridge Approaches | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | |
|---|----------|---------|----------|----------|----------|----------|---------|
| Crosbies Rd from 4.4 to 5.7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Heavy Patching | 0 | 0 | 0 | 0 | 0 | -250000 | -250000 |
| Lower River Rd - 2278-3047 | 0 | 0 | 0 | 0 | 0 | -133000 | 0 |
| Lower River Rd - 3480-4836 | 0 | 0 | 0 | 0 | 0 | -235000 | 0 |
| Lower River Rd - 5415-6813 | 0 | 0 | 0 | 0 | 0 | -242000 | 0 |
| Lower River Rd - 1902-2278 | 0 | 0 | 0 | 0 | 0 | 0 | -78000 |
| Lower River Rd - Causeways 2.8 and 3.2 | -200000 | -200000 | 0 | 0 | 0 | -200000 | 0 |
| Racecourse Rd Toc - 7322-7862 | 0 | 0 | 0 | 0 | -171000 | 0 | 0 |
| Racecourse Rd Toc - 4279-5669 | 0 | 0 | 0 | 0 | 0 | 0 | -345000 |
| Snell Road 00-1225 | 0 | 0 | 0 | 0 | -260000 | 0 | 0 |
| Strathvale Rd | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| South Coree Rd 8320-8777 | 0 | 0 | -112000 | 0 | 0 | 0 | 0 |
| South Coree Rd 0-1742 | 0 | 0 | 0 | 0 | -460000 | 0 | 0 |
| Tuppall Road 1398-1799 | 0 | 0 | 0 | 0 | -98000 | 0 | 0 |
| Woolshed Rd 21.0-22.0 | 0 | 0 | -90000 | -380000 | 0 | 0 | 0 |
| Maxwells Rd - Larkins Rd to Riverina Hwy | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Melrose Rd - 9637 to 10653 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Melrose Rd - 8637-9637 | 0 | 0 | -223000 | 0 | 0 | 0 | 0 |
| Melrose Rd -7570-8637 | 0 | 0 | 0 | -238000 | 0 | 0 | 0 |
| Melrose Rd - 00-4948 (part) | 0 | 0 | 0 | 0 | -265000 | 0 | 0 |
| Coldwells Rd | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Peppertree Rd - to 2.4 to 3.5 from woolshed | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Lawlors Rd Berrigan - Heavy Patching | -70000 | -70000 | 0 | 0 | 0 | 0 | 0 |
| Crosbies Rd - Curves | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Stock Route Road 0-3032 | 0 | 0 | -150000 | -300000 | 0 | 0 | 0 |
| RURAL ROADS CONSTRUCTION EXPENDITURE Total | -1360174 | -915174 | -1353000 | -1328000 | -1444000 | -1360000 | -897000 |
| RURAL ROADS CONSTRUCTION TOTAL | -1360174 | -915174 | -1353000 | -1328000 | -1444000 | -1360000 | -897000 |
| RMS WORKS INCOME | | | | | | | |
| UNGROUPED | | | | | | | |

| | | | | | | | |
|--------------------------|--------|--------|--------|--------|-----------------|--------|--------|
| RMS Block | 175000 | 175000 | 175000 | 175000 | 175000 | 175000 | 175000 |
| RMS Repair | 175000 | 175000 | 175000 | 175000 | 175000 | 175000 | 175000 |
| UNGROUPED Total | 350000 | 350000 | 350000 | 350000 | 350000 | 350000 | 350000 |
| RMS WORKS INCOME Total | 350000 | 350000 | 350000 | 350000 | 350000 | 350000 | 350000 |
| RMS WORKS EXPENDITURE | | | | | | | |
| MR363 -12626.00-14786.00 | | | | | | 233000 | 391000 |
| MR550-17304.00-20569.00 | | | | | | | |
| MR363-1246-1665 | | 170000 | | | | | |
| MR550-2934-3710 | | | | | 113000 | 111000 | |
| MR550-1016-2654 | | | | 113000 | 360000 | | |
| MR363-1665-4250 | | 190000 | 360000 | 197000 | | | |
| MR226-2105-3469 | | 150000 | 150000 | 200000 | Asphalt overlay | | |
| MR564-1957-3419 | | | | | | | |
| MR363-8033-8924 | | | | | | | 119000 |
| MR363-4250-4378 | | | | | 37000 | | |
| MR363-168-744 | | | | | | 166000 | |
| RMS CONSTRUCTION TOTAL | | 510000 | 510000 | 510000 | 510000 | 510000 | 510000 |
| RMS RESEALING | | 350000 | 350000 | 350000 | 350000 | 350000 | 350000 |

RMS WORKS EXPENDITURE Total

R2R GRANT

UNGROUPED

To be determined

1316290.5 1316290.5 987218 987218 987218 987218 987218

R2R GRANT Total

1316290.5 1316290.5 987218 987218 987218 987218 987218

FOOTPATHS INCOME

BAROOGA

Nangunia St - Botanical Gardens to Takari St

0 0 0 0 0 0 0

BAROOGA Total

0 0 0 0 0 0 0

BERRIGAN

Jerilderie St - End of concrete path to Stafford St

14000

Stafford St - Jerilderie St to FlynnSt

1500

Momalong St - Jerilderie St to Davis St

0 5808 0

Jerilderie St - Horsfall St to Orr St

22000

BERRIGAN Total

0 0 0 27808 15500 0 0

FINLEY

Tongs St - Coree St to Murray St

0 0 0 0 0 0 0

Coree St McNamara to Tongs

23000 23000 0 0 0 0 0

| | | | | | | | |
|---|-------|-------|-------|--------|--------|------|------|
| Dawe Ave - Finley Regional Care to Pre-School | 0 | 15000 | 0 | 0 | 0 | 0 | |
| Donaldson Street - Schoullar to Dawe | 0 | 6000 | 0 | 0 | 0 | 0 | |
| Schoullar St - Donaldson to Finley Regional Care | 0 | 0 | 0 | 0 | 0 | 0 | |
| Finley Chamber Walking Track Tongs St | 0 | 0 | 0 | 0 | 0 | 0 | |
| FINLEY Total | 23000 | 44000 | 0 | 0 | 0 | 0 | 0 |
| TOCUMWAL | | | | | | | |
| Jerilderie St Nth | 25000 | 25000 | 0 | 0 | 0 | 0 | |
| SCCF - Extension Path Network | 0 | 0 | 0 | 0 | 0 | 0 | |
| Bruton St - Anthony to Hannah | 0 | 0 | 13500 | 0 | 0 | 0 | |
| Hannah St - Hennessy to Bruton | 0 | 0 | 21500 | 0 | 0 | 0 | |
| Hennessy St - Town Beach Rd to Morris St | | | | | | 7300 | |
| Charlotte St - Bruton St to Hennessy St | | | | 10000 | | | |
| Kelly St - Charlotte St to Jerilderie St | | | | | | | 7500 |
| TOCUMWAL Total | 25000 | 25000 | 35000 | 10000 | 0 | 7300 | 7500 |
| FOOTPATHS INCOME Total | 48000 | 69000 | 35000 | 37808 | 15500 | 7300 | 7500 |
| FOOTPATHS EXPENDITURE | | | | | | | |
| BAROOGA | | | | | | | |
| Nangunia St - Botanical Gardens to Takari St | 0 | 0 | 0 | 0 | 0 | 0 | |
| BAROOGA Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| BERRIGAN | | | | | | | |
| Jerilderie St - End of concrete path to Stafford St | | | | | -45000 | | |
| Stafford St - Jerilderie St to FlynnSt | | | | | -15000 | | |
| Momalong St - Jerilderie St to Davis St | | | 0 | -13200 | 0 | | |
| Jerilderie St - Horsfall St to Orr St | | | | -56400 | | | |
| Hayes Park Toilets Footpath | 0 | 0 | 0 | 0 | 0 | 0 | |

| | | | | | | | |
|--|--------|---------|--------|--------|--------|--------|--------|
| Racecourse Rd - Walking Tr Cobram to Jerilderie | 0 | 0 | 0 | 0 | 0 | 0 | |
| BERRIGAN Total | 0 | 0 | 0 | -69600 | -60000 | 0 | 0 |
| FINLEY | | | | | | | |
| Tong St walking Track | 0 | 0 | 0 | 0 | 0 | | |
| Tongs St - Coree St to Murray St | 0 | 0 | 0 | 0 | 0 | | |
| Coree St McNamara to Tongs | -48000 | -48000 | 0 | 0 | 0 | 0 | |
| Dawe Ave - Finley Regional Care to Pre-School | 0 | -40000 | 0 | 0 | 0 | 0 | |
| Donaldson Street - Schoullar to Dawe | 0 | -13000 | 0 | 0 | 0 | 0 | |
| Scoullar St - Donaldson to Finley Regional Care | 0 | 0 | 0 | 0 | 0 | 0 | |
| Finley St Detention Basin | -20000 | -20000 | 0 | 0 | 0 | 0 | |
| Finley Chamber Walking Track Tongs St | -20000 | -20000 | 0 | 0 | 0 | 0 | |
| FINLEY Total | -88000 | -141000 | 0 | 0 | 0 | 0 | 0 |
| TOCUMWAL | | | | | | | |
| Jerilderie St Nth | -60000 | -60000 | 0 | 0 | 0 | 0 | |
| SCCF - Walking track to Quicks Rd / Babingtons / MR550 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Quicks Rd Walking Track | 0 | 0 | 0 | 0 | 0 | 0 | |
| Bruton St - Anthony to Hannah | 0 | 0 | -30000 | 0 | 0 | 0 | |
| Hannah St - Hennessy to Bruton | 0 | 0 | -45000 | 0 | 0 | 0 | |
| Hennessy St - Town Beach Rd to Morris St | 0 | 0 | 0 | 0 | 0 | -19200 | |
| Charlotte St - Bruton St to Hennessy St | | | | -50000 | | | |
| Kelly St - Charlotte St to Jerilderie St | | | | | | | -66000 |
| TOCUMWAL Total | -60000 | -60000 | -75000 | -50000 | 0 | -19200 | -66000 |
| UNGROUPED | | | | | | | |
| Street Lighting in Towns | -10000 | -10000 | -10000 | -10000 | -10000 | -10000 | -10000 |
| New Footpaths / replace existing | -10000 | -10000 | -50000 | -20000 | -50000 | -80000 | -50000 |
| UNGROUPED Total | -20000 | -20000 | -60000 | -30000 | -60000 | -90000 | -60000 |

| | | | | | | | |
|-----------------------------|---------|---------|---------|---------|---------|---------|---------|
| FOOTPATHS EXPENDITURE Total | -168000 | -221000 | -135000 | -149600 | -120000 | -109200 | -126000 |
| FOOTPATHS NET COST | -120000 | -152000 | -100000 | -111792 | -104500 | -101900 | -118500 |

Appendix E Disposal Summary

E.1 – Disposal Forecast Assumptions and Source

The only assets identified for disposal during life of this plan are components of the transport infrastructure that replaced prior to reaching their adopted useful life. These assets will have no revenue value and the remaining valuation will be written off the asset register as a book entry.

E.2 – Disposal Forecast Summary

Table E3 – Disposal Activity Summary

| Year | Disposals Forecast | Disposal Budget |
|------|--------------------|-----------------|
| 2020 | 0 | 0 |
| 2021 | 0 | 0 |
| 2022 | 0 | 0 |
| 2023 | 0 | 0 |
| 2024 | 0 | 0 |
| 2025 | 0 | 0 |
| 2026 | 0 | 0 |
| 2027 | 0 | 0 |
| 2028 | 0 | 0 |
| 2029 | 0 | 0 |
| 2030 | 0 | 0 |
| 2031 | 0 | 0 |
| 2032 | 0 | 0 |
| 2033 | 0 | 0 |
| 2034 | 0 | 0 |
| 2035 | 0 | 0 |
| 2036 | 0 | 0 |
| 2037 | 0 | 0 |
| 2038 | 0 | 0 |
| 2039 | 0 | 0 |

Appendix F Budget Summary by Lifecycle Activity

Acquisitions will generally be associated with widening of rural roads to adopted service standards or the extension of the kerb and gutter and footpath networks to service the existing residential areas. There will be some donated assets received from property developments, however, there has been no attempt to factor these in as the development rate is unpredictable and they will have only a minor effect on the total asset quantum.

Operational and maintenance costs are expected to increase slightly for the forecast period to service acquisitions and budgets have been prepared to balance expected costs.

The estimates for renewals in this Asset Management Plan were based on the asset register. The average spend that is budgeted generally allows for renewal of assets as required. There is a significant backlog that should be addressed over the coming five years and then progress with renewal will need to be monitored as the mid term of the budget is approached at 2030 when some significant renewals are forecast. It is possible that these issues can be addressed by deferring renewals if condition ratings are favourable or alternatively the budget may have to be increased for this period.

The only assets identified for disposal during life of this plan are components of the transport infrastructure that replaced prior to reaching their adopted useful life. These assets will have no revenue value and the remaining valuation will be written off the asset register as a book entry.

Table F1 – Budget Summary by Lifecycle Activity

| Year | Acquisition | Operation | Maintenance | Renewal | Disposal | Total |
|------|-------------|-------------|-------------|-------------|----------|-------------|
| 2020 | \$741,500 | \$1,223,000 | \$3,146,007 | \$2,159,700 | 0 | \$7,270,207 |
| 2021 | \$514,200 | \$1,244,000 | \$2,619,520 | \$1,807,300 | 0 | \$6,185,020 |
| 2022 | \$718,400 | \$1,249,117 | \$2,630,297 | \$1,784,500 | 0 | \$6,382,314 |
| 2023 | \$652,000 | \$1,253,762 | \$2,640,078 | \$1,890,000 | 0 | \$6,435,840 |
| 2024 | \$478,200 | \$1,257,169 | \$2,647,251 | \$2,251,000 | 0 | \$6,633,620 |
| 2025 | \$496,000 | \$1,260,702 | \$2,654,692 | \$1,742,000 | 0 | \$6,153,394 |
| 2026 | \$460,000 | \$1,263,979 | \$2,661,592 | \$1,950,000 | 0 | \$6,335,571 |
| 2027 | \$460,000 | \$1,267,257 | \$2,668,493 | \$1,930,000 | 0 | \$6,325,750 |
| 2028 | \$460,000 | \$1,270,534 | \$2,675,393 | \$1,930,000 | 0 | \$6,335,927 |
| 2029 | \$460,000 | \$1,273,811 | \$2,682,294 | \$1,930,000 | 0 | \$6,346,105 |
| 2030 | \$460,000 | \$1,277,088 | \$2,689,194 | \$1,930,000 | 0 | \$6,356,282 |
| 2031 | \$460,000 | \$1,280,365 | \$2,696,095 | \$1,980,000 | 0 | \$6,416,460 |
| 2032 | \$410,000 | \$1,283,285 | \$2,702,245 | \$1,980,000 | 0 | \$6,375,530 |
| 2033 | \$410,000 | \$1,286,206 | \$2,708,396 | \$1,980,000 | 0 | \$6,384,602 |
| 2034 | \$410,000 | \$1,289,127 | \$2,714,546 | \$1,980,000 | 0 | \$6,393,673 |
| 2035 | \$410,000 | \$1,292,048 | \$2,720,697 | \$1,980,000 | 0 | \$6,402,745 |
| 2036 | \$410,000 | \$1,294,969 | \$2,726,847 | \$1,980,000 | 0 | \$6,411,816 |
| 2037 | \$410,000 | \$1,297,890 | \$2,732,998 | \$1,980,000 | 0 | \$6,420,888 |
| 2038 | \$410,000 | \$1,300,810 | \$2,739,148 | \$1,980,000 | 0 | \$6,429,958 |
| 2039 | \$410,000 | \$1,303,732 | \$2,745,299 | \$1,980,000 | 0 | \$6,439,031 |